

Notice Inviting Tender

Comprehensive Maintenance of Civil work, Horticulture, Public Health Work, Service of Housekeeping and Round the clock O & M services for public health work at Sonipat Campus of IIT Delhi for the year 2025-2026.

Civil work amount : Rs. 2,90,36,106/-

(WORKS DEPARTMENT)

INDIAN INSTITUTE OF TECHNOLOGY DELHI HAUZ KHAS, NEW DELHI

INDIAN INSTITUTE OF TECHNOLOGY DELHI HAUZ KHAS, NEW DELHI-110016

INDEX

Name of work: - Comprehensive Maintenance of Civil work, Horticulture, Public Health Work, Service of Housekeeping and Round the clock O & M services for public health work at Sonipat Campus of IIT Delhi for the year 2025-2026.

Sl. No.	Description	Page No.
1	Index	2
2.	Notice Inviting e-tender	3
3.	Part A	
	Information and instructions for bidders for e-tendering	4-7
	IITD-6 for e-Tendering and Terms & Conditions	8-23
	Integrity Pact	24-30
	Form of Earnest Money (Bank Guarantee)	31
	Performance Guarantee	32
	Form-F	33
	Annexure- I, II, III	34-36
4.	Part B	
	IITD 7/8 e-Tendering	37-39
	Schedule A-F	40-47
	Special Condition of Contract	48-50
	Guarantee Bond for Water Proofing	51
	List of Approved/Acceptable Make	52-57
	Online Bid Submission	58
5.	Part C	
	Schedule of Quantity	59-77

It is certified that this document contains three parts i.e. Part A, Part B & Part C containing page no. 1 to 77.

Assistant Engineer (C)

Executive Engineer (CD-I)

NIT approved for Rs. 2,90,36,106/- (Rupees Two Crore Ninety Lakhs Thirty-Six Thousand One Hundred Six only)

Institute Engineer

INDIAN INSTITUTE OF TECHNOLOGY DELHI HAUZ KHAS, NEW DELHI-110016

Notice Inviting e - Tender

The Executive Engineer (CD-I), IIT DELHI, HAUZ KHAS, New Delhi-16 (Phone No 011-26596851) on behalf of Board of Governors invite online Item Rate Tender from Firms/ Contractors Registered in appropriate class and category with CPWD, MES, BSNL and Railways for Composite works/ Building and Roads/ Building of the following work:

NIT No. : **120/IITD/EE(CD-I)/2024-25**

Name of Work : Comprehensive Maintenance of Civil work,

Horticulture, Public Health Work, Service of Housekeeping and Round the clock O & M services for public health work at Sonipat Campus of IIT Delhi for

the year 2025-2026.

Estimated cost : **Rs. 2,90,36,106/-**Earnest Money : **Rs. 5,80,722/-**

Performance Guarantee : 5% of Tendered value
Security Deposit : 2.5% of Tendered Value

Period for completion : 12 Months

Late date & time for submission : 19/12/2024 upto15.00 Hrs.

of bids

Date & Time of opening of Bids : 20/12/2024 at 15.30 Hrs.

The bid forms and other details can be obtained from the website <u>www.iitd.ac.in</u> or e-Procure.gov.in free of cost. For more clarification you may visit on above website.

Executive Engineer (CD-I), For & on Behalf of BOG, IIT Delhi

Budget Head: Civil Maintenance of Sonipat Campus/ 31.06.70 (2021/007/0395)

Copy to: -

- 1. Institute Engineer
- 2. Executive Engineer (CD-I) for information.
- 3. D.A. (Works Accounts)
- 4. D.R. (A/Cs) for opening of uploaded documents at 3:30 PM on 20/12/2024 in the office of D.R. Store
- 5. Notice Boards.
- 6. Office Copy
- 7. Web site Administrator, I.I.T.D.

PART 'A'

INDIAN INSTITUTE OF TECHNOLOGY DELHI HAUZ KHAS: NEW DELHI – 110016 IITD/WORKS (SP-4844)/2024

INFORMATION AND INSTRUCTIONS FOR BIDDERS FOR e-TENDERING (Tender Notice)

The Executive Engineer (CD-I), IIT DELHI, HAUZ KHAS, New Delhi-16 (Phone No 011-26596851) on behalf of Board of Governors invite online Item Rate Tender from Firms/ Contractors Registered in appropriate class and category with CPWD, MES, BSNL, and Railways for Composite works/ Building and Roads/ Building of the following work:

SL. No.	NIT No.	Name of Work	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Tender Fees (in Rs.)	Time for Completion
1	120/IITD/EE(CD-I)/2024-25	Comprehensive Maintenance of Civil work, Horticulture, Public Health Work, Service of Housekeeping and Round the clock O & M services for public health work at Sonipat Campus of IIT Delhi for the year 2025- 2026.	2,90,36,106/-	5,80,722/- (To be returned after deposition of P.G)	Nil	12 Months

Last date and time of submission of financial & Technical bid: 19/12/2024 upto 3:00 pm (on line)

Date and time of opening of Technical bid : 20/12/2024 at 3:30 pm (office of D.R Store) Price bids of eligible bidders as per NIT shall be opened at a later date after scrutiny of Technical bids.

- 1. The successful bidders shall be required to submit a performance guarantee of 5% of the tendered amount in the form of Bank Guarantee or F.D.R. from a Nationalized/Scheduled Bank within 15 days of issue of letter of intent before award of work. In case of failure by the Contractor to supply the performance guarantee within the specified period, full earnest money will be forfeited, and the tender shall be treated as void. The performance guarantee shall be initially valid up to the date of completion plus 60 (Sixty) days beyond that.
- **2.** Contractors who fulfill the following requirements shall be eligible to apply. Joint ventures are not accepted.
 - Firms/Contractors must have completed satisfactorily one similar work of value not less than Rs. 2,32,28,900/- or two similar works each of value not less than Rs. 1,74,21,700/-or three similar works each of value not less than Rs 1,16,14,500/-during last 7 years ending on previous day of last date of submission of bid.
 - ii) **Earnest money of Rs. 5,80,722**/-in the form of Banker's cheque or Demand draft or fixed deposit receipt of a schedule bank drawn in favour of **Registrar, I.I.T. Delhi**. No relaxation in EMD will be allowed for MSMEs and MSEs as per CPWD Manual.
- 3. Similar work means successfully completed work of comprehensive maintenance including at least three components from (a). Civil work (b). Horticulture work (c). Housekeeping (d). Public health services work in a single contract.
- **4.** The intending bidder must read the terms and conditions of IITD-6 carefully. He should only submit his bid if he considers himself eligible and he is in possession of all the documents required.
- 5. Information and Instructions for bidders posted on website shall form part of bid document.
- 6. The bid document consisting of plans, specifications, the schedule of quantities of various types of items to be executed and the set of terms and conditions of the contract to be complied with and

- other necessary documents can be seen and downloaded from website http://eprocure.gov.in/eprocure/app.in free of cost.
- 7. Completion certificates issued by an officer not below the rank of Executive Engineer of similar works completed by the Agency.
- **8.** Work means only work under Government/ Central Public Sector Undertaking / State Public Sector Under Central Autonomous bodies/ State Autonomous bodies/ City Development Authority/ Municipal Cooperation of City formed under any act by Central/ State Government and published in Central/ State Gazette.
- 9. The value of executed work shall be brought to current costing level by enhancing the actual value of work at simple rate of 7% per annum calculated from the date of completion to last date of submission of financial bid.
- 10. IITD is committed to follow the principle of transparency, equity, and competitiveness in public procurement. Before submission of bid each bidder should sign integrity pact at respective places and submit the bid, if duly signed integrity pact is not submitted by bidder such bid shall not be considered.
- 11. Those contractors not registered on the website mentioned above, are required to get registered beforehand. If needed they can be imparted training on online bidding process as per details available on the website
- 12. The intending bidder must have valid class-III digital signature to submit the bid.
- 13. On opening date, the contractor can login and see the bid opening process. After opening of bids he will receive the competitor bid sheets.
- **14.** Contractor can upload documents in the form of JPG format and PDF format.
- 15. Contractor must ensure to quote rate of each item, while selecting any of the cells a warning appears that if any cell is left blank the same shall be treated as "0". Therefore, if any cell is left blank and no rate is quoted by the bidder, rate of such item shall be treated as "0" (ZERO).
- 16. The department reserves the right to reject any prospective application without assigning any reason and to restrict the list of qualified contractors to any number deemed suitable by it, if too many bids are received satisfying the laid down criterion.
- 17. In e-Tendering intending bidder can quote his rates in figures only. The rates in words against amount of each item and total is generated automatically. Therefore, the rate quoted by the bidder in figures will be taken as final.
- 18. The bid can only be submitted after uploading the mandatory scanned documents such as Demand Draft or Pay order or Banker's Cheque or Deposit at call Receipt or Fixed Deposit Receipts and towards cost of EMD in favor of **Registrar IIT Delhi** to be deposited with http://eprocure.gov.in/eprocure/app/NEFT facility.
- 19. The physical EMD of the scanned copy of EMD uploaded shall be deposited by the lowest tenderer within a week after opening of financial bid failing which the tender shall be rejected.
- 20. The following undertaking in this regard shall be up-loaded by the intending bidders: "the physical EMD shall be deposited by me / us with the Authority inviting the tender, in case I / we become the lowest tenderer, within a week of the opening of financial bid, otherwise, department may reject the tender and also take action to debar me / us from tendering in any form in IIT Delhi"
- 21. Copy of enlistment order and certificate of work experience and other documents as specified in the Press Notice / web notice shall be scanned and up-loaded to the e-Tendering website within the period of bid submission. However, certified / original copy of all the scanned and up-loaded documents as specified in press notice web / notice shall have to be submitted by the lowest bidder only along with physical EMD of the scanned copy of EMD uploaded within a week physically in the office of e-tendering authority and it shall be sole responsibility of lowest bidder.

- 22. Online bid documents submitted by intending bidders shall be opened only of those bidders, who has deposited EMD and other documents scanned and uploaded are found in order.
- 23. When bids are invited in two /three stages systems and if it is desired to submit revised financial bid it shall be mandatory to submit revised financial bid. If not submitted then the bid submitted earlier shall become invalid Not applicable.
- 24. The bid submitted shall become invalid if:
 - a. The bidder is found ineligible if he fails to upload documents from 1 to 10 on tender notice page 6.
 - b. The bidder does not upload all the documents (including GST registration) as stipulated in the bid document including the undertaking about deposition of physical EMD of the scanned copy of EMD uploaded etc.
 - c. If any discrepancy is noticed between the documents as uploaded at the time of submission of bid and hard copies as submitted physically by the lowest tenderer in the office of tender opening authority.
 - d. The lowest bidder does not deposit physical EMD within a week of opening of tender.
 - e. The Bidder does not upload ESI & EPF Registration.
- 25. Bid validity shall be 75 days from last date of submission of bid.
- **26.** Rate of bidders shall be considered inclusive of GST.

List of Documents to be scanned and uploaded within the period of bid submission:

- 1. Demand Draft/Pay order or Banker's Cheque /Deposit at Call Receipt/FDR of any Scheduled Bank against EMD/ online submission of tender fee and refund of EMD other than lowest.
- 2. Enlistment order of contractor.
- 3. Certificate of work experience.
- 4. Certificate of Registration for GST and acknowledgement of up to date filed return of GST.
- 5. Affidavit on Rs.100/- Non judicial Stamp as per Notice Inviting Tender Condition 1.3 at page 8 of NIT. (Stamp Paper shall be purchased/ notarized between date of publishing and last date of submission of bids beside this NIT/Tender ID and name of work must be mentioned on the affidavit).
- 6. Acceptance to execute INTEGRITY PACT.
- 7. Undertaking as per 'Sl. No. 20 on page No. 5' on firm's letter head.
 - The physical EMD shall be deposited by me / us with the Authority inviting the tender, in case I / we become the lowest tenderer, within a week of the opening of financial bid, otherwise, department may reject the tender and also take action to debar me / us from tendering in any form in IIT Delhi.
- 8. ESI & EPF registration.
- 9. FORM "F" (Duly filled with all required details).
- 10. In case of Partnership firm if all the papers of tender not signed by all the partners than a power of attorney authorizing the person who has signed the tender paper must be uploaded with the tender documents.
- 11. Annexure-I (duly filled & signed by the bidders)
- 12. Annexure-II (duly filled & signed by the bidders)
- 13. Annexure-III (duly filled & signed by the bidders)

Note: - All Documents mentioned S.N-1 to 10 are mandatory for technically qualifying and document mentioned 11 to 13 are not mandatory.

Executive Engineer (CD-I), For & on Behalf of BOG, IIT Delhi Hauz Khas, New Delhi-110016

Budget Head: Civil Maintenance of Sonipat Campus/ 31.06.70 (2021/007/0395)

Copy to: -

- 1. Executive Engineer (CD-I) for information.
- 2. D.A. (Works Accounts)
- 3. D.R. (A/Cs) for opening of tenders on 20/12/2024 at 3:30 PM in the office of D.R. Store
- 4. Notice Boards.
- 5. Office Copy
- 6. Web site Administrator, I.I.T.D
- 7. NIT:- Publicity on Website on Institute as well as on CPP portal http://eprocure.gov.in may be ensured as per instruction issued.
- **8.** E-tendering Web. http://eprocure.gov.in/eprocure/app or wwww.iitd.ac.in

INDIAN INSTITUTE OF TECHNOLOGY DELHI HAUZ KHAS: NEW DELHI – 110016 IITD-6 FOR e-TENDERING ANDTERM&CONDITIONS

Item rate tenders are invited on behalf of Board of Governors from contractors/firms engaged/ register in appropriate category having completed work in appropriate category for the work as per tender notice.

- 1. The enlistment of the contractors should be valid on the last date of submission of tenders. In case the last date of submission of tender is extended, the enlistment of contractor should be valid on the original date of submission of tenders.
- 1.1 The work is estimated to cost **as per tender notice** This estimate, however, is given merely as a rough guide.
- 1.2 Details of criteria for eligibility As Indicated in "INFORMATION AND INSTRUCTIONS FOR CONTRACTORS FOR e- TENDERING FORMING PART OF NIT AND TO BE POSTED ON WEBSITE"
- 1.3 To become eligible for issue of tender, the tenderer shall have to furnish an affidavit as under:-
 - I/We undertake and confirm that eligible similar works(s) has/have not been got executed through another contractor on back to back basis. Further that, if such a violation comes to the notice of Department, then I/we shall be debarred for tendering in IITD in future forever. Also, if such a violation comes to the notice of Department before date of start of work, the Engineer-in-Charge shall be free to forfeit the entire amount of Earnest Money Deposit/Performance Guarantee. (Scanned copy to be uploaded at the time of submission of bid)
 - 2. Agreement shall be drawn with the successful bidders on prescribed Form No. IITD 8 (or other Standard Form as mentioned) which is available as a Govt. of India Publication. Bidders shall quote his rates as per various terms and conditions of the said form which will form part of the agreement.
 - 3. The time allowed for carrying out the work will be **as per tender notice** from the date of start as defined in schedule 'F' or from the first date of handing over of the site, whichever is later, in accordance with the phasing, if any, indicated in the tender documents.

4. The site for the work is available.

- 5. The bid document consisting of plans, specifications, the schedule of quantities of various types of items to be executed and the set of terms and conditions of the contract to be complied with and other necessary documents except Standard General Conditions of Contract Form can be seen from the web Site http://eprocure.gov.in/eprocure/appor iitd.ac.in or e-procure.gov **free** of cost.
- 6. After submission of the bid the contractor can re-submit revised bid any number of times but before last time and date of submission of tender as notified.
- 7. While submitting the revised bid, contractor can revise the rate of one or more item(s) any number of times (he need not re-enter rate of all the items) but before last time and date of submission of tender as notified.
- 8. If it is desired to submit revised financial bid then it shall be mandatory to submit revised financial bid. If not submitted then the tender submitted earlier shall become invalid.
- 9. Earnest Money in the form of Demand Draft or Pay order or Banker's Cheque or Deposit at Call Receipt (drawn in favour of Registrar IIT Delhi, Hauz Khas, New Delhi) as specified of any Scheduled/Nationalized Bank and shall be scanned & uploaded to the e- tendering website within the period of tender submission or through RTGS/NEFT with UTR details and original should be deposited by lowest bidder within a week after the opening of financial bid in office of Executive Engineer (CD-I), IIT Delhi, Hauz Khas, New Delhi

A part of earnest money is acceptable in the form of bank guarantee also. In such case, 50% of earnest money or Rs. 20 lakh, whichever is less, will have to be deposited in shape prescribed above, and balance in shape of Bank Guarantee of any scheduled bank which is to be scanned and uploaded by the intending

bidders.

Interested contractor who wish to participate in the bid has also to make following payments in the form of Demand Draft/Pay order or Banker's Cheque of any Scheduled Bank and to be scanned and uploaded to the e-Tendering website within the period of bid submission:

http://eprocure.gov.in/eprocure/app.

- 10. The bid submitted shall become invalid if:
 - a. The bidder is found ineligible if he fails to upload documents from 1 to 10 on tender notice page
 6.
 - b. The bidder does not upload all the documents (including GST registration) as stipulated in the bid document including the undertaking about deposition of physical EMD of the scanned copy of EMD uploaded etc.
 - c. If any discrepancy is noticed between the documents as uploaded at the time of submission of bid and hard copies as submitted physically by the lowest tenderer in the office of tender opening authority.
 - d. The lowest bidder does not deposit physical EMD within a week of opening of tender.
 - e. The Bidder does not upload ESI & EPF Registration.
- 11. The time & date of submission & opening of financial bid of contractors qualifying the **criteria as per Tender Notice** shall be communicated to them at a later date.
- 12. The contractor whose bid is accepted, will be required to furnish performance guarantee of 5% (Five Percent) of the tendered and accepted of the bided amount within the period specified in Schedule F. This guarantee shall be in the form of cash (in case guarantee amount is less than Rs. 10000/-) or Deposit at Call receipt of any scheduled bank/Banker's cheque of any scheduled bank/ Demand Draft of any scheduled bank/Pay order of any Scheduled Bank of any scheduled bank (in case guarantee amount is less than Rs. 1,00,000/-) or Government Securities or Fixed Deposit Receipts or irrevocable Bank Guarantee Bonds of any Scheduled Bank or the State Bank of India in accordance with the prescribed form. In case the contractor fails to deposit the said performance guarantee within the period as indicated in Schedule 'F' including the extended period if any, the Earnest Money deposited by the contractor shall be forfeited automatically without any notice to the contractor.
- 13. Intending Bidders are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their tenders as to the nature of the ground and sub-soil (so far as is practicable), the form and nature of the site, the means of access to the site, the accommodation they may require and in general shall themselves obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their tender. A tenderer shall be deemed to have full knowledge of the site whether he inspects it or not and no extra charge consequent on any misunderstanding or otherwise shall be allowed. The tenderer shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, electricity access, facilities for workers and all other services required for executing the work unless otherwise specifically provided for in the contract documents. Submission of a tender by a tenderer implies that he has read this notice and all other contract documents and has made himself aware of the scope and specifications of the work to be done and of conditions and rates at which stores, tools and plant, etc. will be issued to him by the Government and local conditions and other factors having a bearing on the execution of the work.
- 14. The competent authority on behalf of the Board of Governors does not bind itself to accept the lowest or any other tender and reserves to itself the authority to reject any or all the tenders received without the assignment of any reason. All tenders in which any of the prescribed condition is not fulfilled or any condition including that of conditional rebate is put forth by the tenderer shall be summarily rejected.
- 15. Canvassing whether directly or indirectly, in connection with tenderers is strictly prohibited and the tenders submitted by the contractors who resort to canvassing will be liable to rejection.
- 16. The competent authority on behalf of Board of Governors reserves to himself the right of accepting the whole or any part of the tender and the tenderer shall be bound to perform the same at the rate quoted.
- 17. The contractor shall not be permitted to tender for works in the IITD responsible for award and execution of contracts, in which his near relative is posted a Divisional Accountant or as an officer in any capacity between the grades of Superintending Engineer and Junior Engineer (both inclusive). He shall also intimate

the names of persons who are working with him in any capacity or are subsequently employed by him and who are near relatives to any gazetted officer in the Central Public Works Department or in the Ministry of Urban Development. Any breach of this condition by the contractor would render him liable to be removed from the approved list of contractors of this Department.

- 18. No Engineer of gazetted rank or other Gazetted Officer employed in Engineering or Administrative duties in an Engineering Department of the Government of India is allowed to work as a contractor for a period of one year after his retirement from Government service, without the previous permission of the Government of India in writing. This contract is liable to be cancelled if either the contractor or any of his employees is found any time to be such a person who had not obtained the permission of the Government of India as afore said before submission of the tender or engagement in the contractor's service.
- 19. The tender for the works shall remain open for acceptance for a period of Seventy Five (75) days from last date of submission of bid, if any tenderer withdraws his tender before the said period or issue of letter of acceptance, whichever is earlier, or makes any modifications in the terms and conditions of the tender which are not acceptable to the department, then the Government shall, without prejudice to any other right or remedy, be at liberty to forfeit 50% of the said earnest money as aforesaid. Further the tenderer shall not be allowed to participate in the retendering process of the work.
- 20. This notice inviting Tender shall form a part of the contract document. The successful tenderer / contractor, on acceptance of his tender by the Accepting Authority shall within 10 days from the stipulated date of start of the work, sign the contract consisting of:
 - a) The Notice Inviting Tender, all the documents including additional conditions, specifications and drawings, if any, forming part of the tender as uploaded at the time of invitation of tender and the rates quoted online at the time of submission of bid and acceptance thereof together with any correspondence leading thereto.
 - b) Standard IITD Form 8 or other Standard IITD Form as mentioned.
- 21. In case any discrepancy is noticed between the documents as uploaded at the time of submission of the bid online and hard copies as submitted physically in the office of Executive Engineer, then the bid submitted shall become invalid.

Executive Engineer (CD-I) IIT Delhi, Hauz Khas New Delhi - 110016

NOTICE INVITING TENDER

INDIAN INSTITUTE OF TECHNOLOGY DELHI

HAUZ KHAS, NEW DELHI-110016

Terms & Conditions

Indian Institute of Technology Delhi is in the process of purchasing following item(s) as per details as given as under.

Details of the item	As per Tender Notice
Earnest Money Deposit to be submitted	Rs. 5,80,722/-
Warranty	As per Tender Notice, NIT & IITD form 8
Performance security	As per Tender Notice, NIT & IITD form 8

Tender Documents may be downloaded from Central Public Procurement Portal http://eprocure.gov.in/eprocure/app. Aspiring Bidders who have not enrolled / registered in e-procurement should enroll / register before participating through the website http://eprocure.gov.in/eprocure/app. The portal enrolment is free of cost. Bidders are advised to go through instructions provided at 'Instructions for online Bid Submission '.

Tenderers can access tender documents on the website (For searching in the NIC site, kindly go to Tender Search option and type 'IIT'. Thereafter, Click on "GO" button to view all IIT Delhi tenders). Select the appropriate tender and fill them with all relevant information and submit the completed tender document online on the website http://eprocure.gov.in/eprocure/app as per the schedule given in the next page.

No manual bids will be accepted. All quotes (both Technical and Financial should be submitted in the E-procurement portal).

Schedule

Name of Organization		Indian Institute of Technology, Delhi							
Tender Type (Open/Limited/EC	OI/Auction/Single)	Open							
Tender Category (Services/Goo	ds/works)	Works							
Type/Form of Contract (Work/S Auction/Service/Buy/Empanelm	* * *	Works							
Product Category (Civil Works/ Works/Fleet Management/ Com		Civil Works.							
Source of Fund (Institute/Project	t)	Budget Head: Civil Maintenance of Sonipat Campus/ 31.06.70 (2021/007/0395)							
Is Multi Currency Allowed		No							
Date of Issue/Publishing		10/12/2024 (17.00 Hrs)							
Document Download/Sale Start	Date	10/12/2024 (17.00 Hrs)							
Document Download/Sale End	Date	19/12 /2024 (15.00 Hrs)							
Date for Pre-Bid Conference		Nil							
Venue of Pre-Bid Conference									
Last Date and Time for Uploadi	ng of Bids	19/12/2024 (15.00 Hrs)							
Date and Time of Opening of To	echnical Bids	20/12/2024 (15.30 Hrs)							
Tender Fee	Nil	(To be paid through RTGS/NEFT. IIT Delhi Bank details at as under:							
EMD	Rs. 5,80,722/-	Name of the Bank A/C: Registrar IIT Delhi SBI A/C No. 10773572622 Name of the Bank : State Bank of India, IIT Delhi, Hauz Khas, New Delhi-110016 IFSC Code : SBIN0001077 MICR Code :110002156 Swift No. : SBININBB547 (This is mandatory that UTR Number is provided in the online quotation/bid. (Kindly refer to the UTR Column of the Declaration Sheet at Annexure-II) or as per NIT/ Tender notice							
No. of Covers (1/2/3/4)		02							
Bid Validity days (180/120/90/7	75/60/30)	75 days (From last date of Submission of bid)							
Address for Communication		Office of the Executive Engineer (CD-I), Room No. AD- 117A, Academic Building, IIT Delhi, Hauz Khas, New Delhi-110016							
Contact No.		011-26596851							
Fax No.		Nil							
Email Address		a26840@admin.iitd.ac.in, a26897@admin.iitd.ac.in							

C----NIL I----NIL O--- NIL

Instructions for Online Bid Submission:

As per the directives of Department of Expenditure, this tender document has been published on the Central Public Procurement Portal (<u>URL:http://eprocure.gov.in/eprocure/app)</u>. The bidders are required to submit soft copies of their bids electronically on the CPP Portal, using valid Digital Signature Certificates. The instructions given below are meant to assist the bidders in registering on the CPP Portal, prepare their bids in accordance with the requirements and submitting their bids online on the CPP Portal.

More information useful for submitting online bids on the CPP Portal may be obtained at: http://eprocure.gov.in/eprocure/app

REGISTRATION

- 1) Bidders are required to enroll on the e-Procurement module of the Central Public Procurement Portal (URL: http://eprocure.gov.in/eprocure/app) by clicking on the link "Click here to Enroll". Enrolment on the CPP Portal is free of charge.
- 2) As part of the enrolment process, the bidders will be required to choose a unique username and assign a password for their accounts.
- 3) Bidders are advised to register their valid email address and mobile numbers as part of the registration process. These would be used for any communication from the CPP Portal.
- 4) Upon enrolment, the bidders will be required to register their valid Digital Signature Certificate (Class II or Class III Certificates with signing key usage) issued by any Certifying Authority recognized by CCA India (e.g. Sify / TCS / nCode / eMudhra etc.), with their profile.
- 5) Only one valid DSC should be registered by a bidder. Please note that the bidders are responsible to ensure that they do not lend their DSCs to others which may lead to misuse.
- 6) Bidder then logs in to the site through the secured log-in by entering their userID / password and the password of the DSC / eToken.

SEARCHING FOR TENDER DOCUMENTS

- 1) There are various search options built in the CPP Portal, to facilitate bidders to search active tenders by several parameters. These parameters could include Tender ID, organization name, location, date, value, etc. There is also an option of advanced search for tenders, wherein the bidders may combine a number of search parameters such as organization name, form of contract, location, date, other keywords etc. to search for a tender published on the CPP Portal.
- 2) Once the bidders have selected the tenders they are interested in, they may download the required documents / tender schedules. These tenders can be moved to the respective 'My Tenders' folder. This would enable the CPP Portal to intimate the bidders through SMS / e-mail in case there is any corrigendum issued to the tender document.
- 3) The bidder should make a note of the unique Tender ID assigned to each tender, in case they want to obtain any clarification / help from the Helpdesk.

PREPARATION OF BIDS

- 1) Bidder should take into account any corrigendum published on the tender document before submitting their bids.
- 2) Please go through the tender advertisement and the tender document carefully to understand the documents required to be submitted as part of the bid. Please note the number of covers in which the bid documents have to be submitted, the number of documents including the names and content of each of the document that need to be submitted. Any deviations from these may lead to rejection of the bid.
- 3) Bidder, in advance, should get ready the bid documents to be submitted as indicated in the tender document / schedule and generally, they can be in PDF / XLS / RAR / DWF formats. Bid documents may be scanned with 100 dpi with black and white option.

4) To avoid the time and effort required in uploading the same set of standard documents which are required to be submitted as a part of every bid, a provision of uploading such standard documents (e.g. PAN card copy, annual reports, auditor certificates etc.) has been provided to the bidders. Bidders can use "My Space" area available to them to upload such documents. These documents may be directly submitted from the "My Space" area while submitting a bid, and need not be uploaded again and again. This will lead to a reduction in the time required for bid submission process.

SUBMISSION OF BIDS

- 1) Bidder should log into the site well in advance for bid submission so that he/she upload the bid in time
 - i.e., on or before the bid submission time. Bidder will be responsible for any delay due to other assues.
- 2) The bidder has to digitally sign and upload the required bid documents one by one as indicated in the tender document.
- 3) The bidder has to select the payment option as "on-line" to pay the tender fee / EMD as applicable and enter details of the instrument. Whenever, EMD / Tender fees is sought, bidders need to pay the tender fee and EMD separately on-line through RTGS (Refer to Schedule, Page No.2).
- 4) A standard BoQ format has been provided with the tender document to be filled by all the bidders. Bidders are requested to note that they should necessarily submit their financial bids in the format provided and no other format is acceptable. Bidders are required to download the BoQ file, open it and complete the white coloured (unprotected) cells with their respective financial quotes and other details (such as name of the bidder). No other cells should be changed. Once the details have been completed, the bidder should save it and submit it online, without changing the filename. If the BoQ file is found to be modified by the bidder, the bid will be rejected.

OR

In some cases Financial Bids can be submitted in PDF format as well (in lieu of BOQ).

- 5) The server time (which is displayed on the bidders' dashboard) will be considered as the standard time for referencing the deadlines for submission of the bids by the bidders, opening of bids etc. The bidders should follow this time during bid submission.
- 6) All the documents being submitted by the bidders would be encrypted using PKI encryption techniques to ensure the secrecy of the data. The data entered cannot be viewed by unauthorized persons until the time of bid opening. The confidentiality of the bids is maintained using the secured Socket Layer 128 bit encryption technology. Data storage encryption of sensitive fields is done.
- 7) The uploaded tender documents become readable only after the tender opening by the authorized bid openers.
- 8) Upon the successful and timely submission of bids, the portal will give a successful bid submission message & a bid summary will be displayed with the bid no. and the date & time of submission of the bid with all other relevant details.
- 9) Kindly add scanned PDF of all relevant documents in a single PDF file of compliance sheet.

ASSISTANCE TO BIDDERS

- 1. Any queries relating to the tender document and the terms and conditions contained therein should be addressed to the Tender Inviting Authority for a tender or the relevant contact person indicated in the tender.
- 2. Any queries relating to the process of online bid submission or queries relating to CPP Portal in general may be directed to the 24x7 CPP Portal Helpdesk. The contact number for the helpdesk is 1800 233 7315.

General Instructions to the Bidders

- 1) The tenders will be received online through portal http://eprocure.gov.in/eprocure/app . In the Technical Bids, the bidders are required to upload all the documents in .pdf format.
- 2) Possession of a Valid Class II/III Digital Signature Certificate (DSC) in the form of smart card/e-token in the company's name is a prerequisite for registration and participating in the bid submission activities through https://eprocure.gov.in/eprocure/app. Digital Signature Certificates can be obtained from the authorized certifying agencies, details of which are available in the web site https://eprocure.gov.in/eprocure/app under the link "Information about DSC".
- 3) Tenderer are advised to follow the instructions provided in the 'Instructions to the Tenderer for the e- submission of the bids online through the Central Public Procurement Portal for e-Procurement at https://eprocure.gov.in/eprocure/app.

Terms & Conditions Details

S.No.	Specification
1.	Due date : The tender must be submitted on-line before the due date. The offers received after the due date and time will not be considered. No manual bids will be considered.
2.	Preparation of Bids : The offer/bid should be submitted in two bid systems (i.e.) Technical bid and financial bid. The technical bid should consist of all technical details along with commercial terms and conditions. Financial bid should indicate item wise price for the items mentioned in the technical bid in the given format i.e BOQ_XXXX.
	OR
	Financial Bids to be submitted in Excel.
	The Technical bid and the financial bid should be submitted Online.
3.	EMD (if applicable): As per NIT
4.	Refund of EMD :- As per NIT
5.	Opening of the tender: As per Tender Notice, NIT & IITD form 8
6.	Acceptance/ Rejection of bids: The competent authority of IIT Delhi reserves the right to reject any or all offers without assigning any reason.
7.	Pre-qualification criteria: - Mentioned in Tender notice
8.	Performance Security:-Mentioned in Tender notice
9.	Force Majeure :- As per IITD form 8
10.	Risk & Cost Clause : As per IITD form 8
11.	Delivery and Documents: As per Tender Notice & NIT & IITD form 8
12.	Delayed delivery: As per Tender Notice & NIT & IITD form 8
13.	Prices: As per Tender Notice & NIT & IITD form 8
14.	Progress of Work :As per Tender Notice & NIT & IITD form 8
15.	Inspection and Tests: As per Tender Notice & NIT & IITD form 8
16.	Resolution of Disputes: As per Tender Notice & NIT & IITD form 8
17.	Applicable Law: As per Tender Notice & NIT & IITD form 8
18.	Supplier Integrity : As per Tender Notice & NIT & IITD form 8
19.	Training : As per Tender Notice & NIT & IITD form 8
20.	Installation & Demonstration : As per Tender Notice & NIT & IITD form 8

21.	Incidental services: As per Tender Notice & NIT & IITD form 8
22.	Defect liability Period : As per Tender Notice & NIT & IITD form 8
23.	Governing Language : As per Tender Notice & NIT & IITD form 8
24.	Applicable Law: As per Tender Notice & NIT & IITD form 8
25.	Notices : As per Tender Notice & NIT & IITD form 8
26.	Taxes: As per Tender Notice & NIT & IITD form 8
27.	Termination for Default : As per Tender Notice & NIT & IITD form 8
28.	Disputes and Jurisdiction: As per Tender Notice & NIT & IITD form 8
29.	Completion certificate: As per Tender Notice & NIT & IITD form 8

Bid Submission

Online Bid Submission:

The Online bids (complete in all respect) must be uploaded online in two Envelops as explained below:-

Bid Docui	ment – 1		
(Following	g documents to be p	rovided as single PDF file)	
Sl. No.	Documents	Content	File
			Types
1.		Compliance Sheet as per Annexure – I	.PDF
2.		Organization Declaration Sheet as per Annexure – II	.PDF
3.	Technical Bid	List of organizations/ clients where the same products have been supplied (in last two years) along with their contact number(s). (Annexure-III)	.PDF
4.		Technical supporting documents in support as per Page-6 of NIT	.PDF
Bid Docui	ment – 2		
Sl. No.	TYPES	Content	
1.	Financial Bid	Price bid should be submitted in Excel format.	.xls

I.I.T.D- 6 FOR e-TENDERING

I.I.T.D

INDIAN INSTITUTE OF TECHNOLOGY, DELHI HAUZ KHAS, NEW DELHI -110016 NOTICE INVITING TENDER

Item rate tenders are invited on behalf of The Board of Governors, I.I.T. Delhi, Hauz Khas, New Delhi - 16 from approved and eligible contractors of **CPWD** and those of appropriate class of **M.E.S.**, **BSNL** and **Railway** dealing with for the work of **Comprehensive Maintenance** of Civil work, Horticulture, Public Health Work, Service of Housekeeping and Round the clock **O & M services for public health work at Sonipat Campus of IIT Delhi for the year 2025-2026.**

- 1. The enlistment of the contractors should be valid on the last date of submission of tenders.

 In case only the last date of submission of tender is extended, the enlistment of contractor should be valid on the original date of submission of tenders.
- 1.1 The work is estimated to cost Rs. 2,90,36,106/- This estimate, however, is given merely as a rough guide.
- **1.1.1** The authority competent to approve NIT for the combined cost and belonging to the major discipline will consolidate NITs for calling the bids. He will also nominate Division which will deal with all matters relating to the invitation of bids.
 - For composite bid, besides indicating the combined estimated cost put to tender, should clearly indicates the estimated cost of each component separately. The eligibility of bidders will correspond to the combined estimated cost of different components put to bid.
- 1.2 Intending bidder is eligible to submit the bid provided he has definite proof from the appropriate authority, which shall be to the satisfaction of the competent authority, of having satisfactorily completed similar works of magnitude specified below: -

Criteria of eligibility for submission of bid documents.

1.2.1 Criteria of eligibility for CPWD as well as non-CPWD contractors.

Three similar works each of value not less than 40% of estimated cost or two similar work each of value not less than 60% of estimated cost or one similar work of value not less than 80% of estimated cost (value of work as mentioned in tender notice) during last 7 years ending on previous day of last day of submission of bids.

The value of executed works shall be brought to current costing level by enhancing the actual value of work at simple rate of 7% per annum, calculated during last 7 years ending on previous day of last day of submission of bids.

I.I.T.D – 6 FOR e-TENDERING

I.I.T.D

1.2.2 To become eligible for issue of bid, the bidders shall have to furnish an affidavit as under:

I/We undertake and confirm that eligible similar works(s) has/have not been got executed through another contractor on back to back basis. Further that, if such a violation comes to the notice of Department, then I/we shall be debarred for bidding in I.I.T.D in future forever. Also, if such a violation comes to the notice of Department before date of start of work, the Engineer- in-Charge shall be free to forfeit the entire amount of Performance Guarantee.

- 2. Agreement shall be drawn with the successful bidders on prescribed Form No. I.I.T.D 7/8 which is available as I.I.T.D. Publication. Bidders shall quote their rates as per various terms and conditions of the said form which will form part of the agreement.
- 3. The time allowed for carrying out the work will be **as per Tender Notice** from the date of start as defined in schedule 'F' or from the first date of handing over of the site, whichever is later, in accordance with the phasing, if any, indicated in the bid documents.
- 4. The site for the work shall be made available in parts as and when the site will be available.
- 5. The bid document consisting of plans, specifications, the schedule of quantities of various types of items to be executed and the set of terms and conditions of the contract to be complied with and other necessary documents except Standard General Conditions of Contract Form can be seen from the web Site www.iitd.ac.in or e-procure.gov.in free of cost.
- 6. After submission of the bid the contractor can re-submit revised bid any number of times but before last time and date of submission of tender as notified.
- 7. While submitting the revised bid, contractor can revise the rate of one or more item(s) any number of times (he need not re-enter rate of all the items) but before last time and date of submission of tender as notified.
- 8. If it is desired to submit revised financial bid, then it shall be mandatory to submit revised financial bid. If not submitted, then the tender submitted earlier shall become invalid.

Copy of Enlistment Order and certificate of work experience and other documents as specified in the press notice / web notice shall be scanned and uploaded to the tender website within the period of bid submission. However, certified copy of all the scanned and uploaded documents as specified in press notice / web notice shall have to be submitted by the lowest bidder in the office of tendering authority.

Online bid documents submitted by intending bidders shall be opened only of those bidders, who has deposited tender online fees with and earnest money deposit and other documents scanned and uploaded are found in order. The bid submitted shall become invalid &Tender fees shall not be refunded if:

- (i) The bidder is found ineligible.
- (ii) The bidder does not upload all the documents as stipulated in the bid documents.
- (iii) If any discrepancy is noticed between the documents as uploaded at the time of submission of bid and hard copies as submitted physically by the lowest tenderer in the office of tender opening authority.
- 9. The contractor whose bid is accepted will be required to furnish **performance guarantee of** 5% (Five Percent) of the bid amount within the period specified in Schedule F. This guarantee shall be in the form of cash (in case guarantee amount is less than Rs. 10,000/-) or Deposit at Call receipt of any scheduled bank/Banker's cheque of any scheduled bank/

I.I.T.D – 6 FOR e-TENDERING

I.I.T.D

Demand Draft of any scheduled bank/Pay order of any Scheduled Bank (in case guarantee amount is less than Rs.1,00,000/-) or Government Securities or Fixed.

Deposit Receipts or irrevocable Bank Guarantee Bonds of any Scheduled Bank or the State Bank of India in accordance with the prescribed form. In case the contractor fails to deposit the said performance guarantee within the period as indicated in Schedule 'F' including the extended period if any, the Earnest Money deposited by the contractor shall be forfeited automatically without any notice to the contractor

- 10. Intending Bidders are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their bids as to the nature of the ground and subsoil (so far as is practicable), the form and nature of the site, the means of access to the site, the accommodation they may require and in general shall themselves obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their bid. A bidder shall be deemed to have full knowledge of the site whether he inspects it or not and no extra charge consequent on any misunderstanding or otherwise shall be allowed. The bidders shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, electricity access, facilities for workers and all other services required for executing the work unless otherwise specifically provided for in the contract documents. Submission of a bid by a bidder implies that he has read this notice and all other contract documents and has made himself aware of the scope and specifications of the work to be done and of conditions and rates at which stores, tools and plant, etc. will be issued to him by the Government and local conditions and other factors having a bearing on the execution of the work.
- 11. The competent authority on behalf of the Board of Governors does not bind itself to accept the lowest or any other bid and reserves to itself the authority to reject any or all the bids received without the assignment of any reason. All bids in which any of the prescribed condition is not fulfilled or any condition including that of conditional rebate is put forth by the bidder shall be summarily rejected.
- 12. Canvassing whether directly or indirectly, in connection with bidders is strictly prohibited and the bids submitted by the contractors who resort to canvassing will be liable to rejection.
- 13. The competent authority on behalf of Board of Governors reserves to himself the right of accepting the whole or any part of the bid and the bidder shall be bound to perform the same at the rate quoted.
- 14. The contractor shall not be permitted to bid for works in the IITD responsible for award and execution of contracts, in which his near relative is posted a Divisional Accountant or as an officer in any capacity between the grades of Superintending Engineer and Junior Engineer (both inclusive). He shall also intimate the names of persons who are working with him in any capacity or are subsequently employed by him and who are near relatives to any gazetted officer in the IIT Delhi. Any breach of this condition by the contractor would render him liable to be debarred from bidding process in future in IIT Delhi.
- 15. No Engineer of gazetted rank or other Gazetted Officer employed in Engineering or Administrative duties in an Engineering Department of the Government of India is allowed to work as a contractor for a period of one year after his retirement from Government service, without the prior permission of the Government of India in writing. This contract is liable to be cancelled if either the contractor or any of his employees is found any time to be such a person who had not obtained the permission of the Government of India as aforesaid before

I.I.T.D - 6 FOR e-TENDERING

I.I.T.D

submission of the bid or engagement in the contractor's service.

- 16. The bid for the works shall remain open for acceptance for a period of **Seventy Five** (75) days from the last date of submission of bid, if any bidder withdraws his bid before the said period or issue of letter of acceptance, whichever is earlier, or makes any modifications in the terms and conditions of the bid which are not acceptable to the department, then the IIT Delhi shall, without prejudice to any other right or remedy, the bidder shall debarred for tendering in IIT Delhi for a period of one year.
- 17. This notice inviting bid shall form a part of the contract document. The successful bidder / contractor, on acceptance of his bid by the Accepting Authority shall within 15 days from the stipulated date of start of the work, sign the contract consisting of:
 - a) The Notice Inviting Bid, all the documents including additional conditions, specifications and drawings, if any, forming part of the bid as uploaded at the time of invitation of bid and the rates quoted online at the time of submission of bid and acceptance thereof together with any correspondence leading thereto.
 - b) Standard IITD Form –7/8 or other Standard IITD Form as mentioned.
- 18. In case any discrepancy is noticed between the documents as uploaded at the time of submission of the bid online and hard copies as submitted physically in the office of Executive Engineer, then the bid submitted shall become invalid and the IIT Delhi shall without prejudice to any other right or remedy, the bidder shall debarred for tendering in IIT Delhi for a period of one year.
- 19. **For Composite Bid**
- 19.1 The **Executive Engineer [CD-I]** shall be Engineer-in-charge of the major component and will call the bids for the composite work, Earnest Money will be fixed with respect of the combined estimate cost put to tender for the composite bid.
- 19.2 The bid document will include following three components: -
 - **Part A-** IITD-6, IITD-7 including schedule A to F for the major component of the work. Standard General Conditions of contract for CPWD 2020 as corrected/modified up to date.
 - **Part B** General/Specific conditions, specifications and schedule of quantities applicable to major component of the work.
 - **Part C: -** Schedule A to F for minor component of the work I.E. (Institute Engineer/EE incharge of major component shall also be competent authority under clause 2 and clause 5 as mentioned as schedule A to F to major components), General/ specific conditions, specifications, and schedule of quantities applicable to minor component(s) of the work.
- 19.3 The bidder must associate himself with experienced agencies of the appropriate class eligible for bid for each of the minor component individually.
- 19.4 The eligible bidders shall quote rates for all items of major component as well as for all items of minor component of work.

I.I.T.D – 6 FOR e-TENDERING

- 19.5 After acceptance of the bid by Component authority, the EE [Civil] of the work shall issue letter of award on behalf of the Board of Governors, IIT Delhi, After the work is awarded, the main contractor will have to enter into agreement with EE [Civil] and has to sign two or more copies of agreement.
- 19.6 Entire work under the scope of composite bid including major and all minor components shall be executed under one agreement.
- 19.7 Security Deposit will be worked out separately for each component corresponding to the estimated cost of the respective component of works. The Earnest Money will become part of security deposit of the major component of work.
- 19.8 The main contractor has to associate agency(s) for minor component (s) conforming to eligibility criteria as defined in the bid document and has to submit detail of such agency (s) to Engineer-in-charge of minor component(s) within prescribed time, Name of agency (s) to be associated shall be approved by Engineer-in-charge of minor component(s).
- 19.9 In case the main contractor changes any of the above agency/agencies during the operation of the contract, he shall obtain prior approval of the Engineer-in-charge of minor component. The new agency/agencies shall also have an agency, he can direct the contractor to change the agency executing such items of work and this shall be binding on the contractor.
- 19.10 The main contractor has to enter into agreement with contractor(s) associated by him for execution of minor components(s) in case the main contractor does not have capability to execute the minor component work. Copy of such agreement shall be submitted to EE[CD-I]. In case of change of associate contractor, the main contractor has to enter into agreement with the new contractor associated by him.
- **19.11** Running payment for the major component shall be processed by EE (CD-I).
- 19.12A The composite work shall be treated as completed when all the components of the work are complete and certified. The completion certificate of the composite work shall be recorded by Engineers-in-charge of major component after record of completion certificate of all other components.
- 19.12B Final bill of whole work shall be finalized and paid by the EE (CD-I).

To a second seco	
INTEGRATY PACT e-TENDERING	I.I.T.D

To,																														
	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	٠,	j
		•		•	•		•			•	•		•	•		•	•		•	•		•	•		•		•	•	٠,	,

Subject: - Comprehensive Maintenance of Civil work, Horticulture, Public Health Work, Service of Housekeeping and Round the clock O & M services for public health work at Sonipat Campus of IIT Delhi for the year 2025-2026.

NIT No.:- 120/IITD/EE(CD-I)/2024-25

Dear Sir,

It is here by declared that I.I.T.D is committed to follow the principle of transparency, equity, and competitiveness in public procurement.

The subject Notice Inviting Tender (NIT) is an invitation to offer made on the condition that the Bidder will sign the integrity Agreement, which is an integral part of tender/bid documents, failing which the tenderer / bidder will stand disqualified from the tendering process and the bid of the bidder would be summarily rejected.

This declaration shall form part and parcel of the Integrity Agreement and signing of the same shall be deemed as acceptance and signing of the Integrity Agreement on behalf of the I.I.T.D.

Yours faithfully

Executive Engineer (CD-I)

ACCEPTANCE TO EXECUTE INTEGRITY PACT

I.I.T.D

(To be signed by bidder and upload the scanned copy)

To, Executive Engineer (CD- I) IIT Delhi, Hauz Khas, New Delhi – 110016.

Subject: - Submission of bid for the work of Comprehensive Maintenance of Civil work, Horticulture, Public Health Work, Service of Housekeeping and Round the clock O & M services for public health work at Sonipat Campus of IIT Delhi for the year 2025-2026.

Dear Sir.

I/We acknowledge that I.I.T.D is committed to follow the principles thereof as enumerated in the Integrity Agreement enclosed with the tender/bid document.

I/We agree that the Notice Inviting Tender (NIT) is an invitation to offer made on the condition that I/We will sign the enclosed integrity Agreement, which is an integral part of tender / bid documents, failing which I/We will stand disqualified from the tendering process. I/We acknowledge that THE MAKING OF THE BID SHALL BE REGARDED AS AN UNCONDITIONAL AND ABSOLUTE ACCEPTANCE of this condition of the NIT.

I/We confirm acceptance and compliance with the Integrity Agreement in letter and spirit and further agree that execution of the said Integrity Agreement shall be separate and distinct from the main contract, which will come into existence when tender/bid is finally accepted by I.I.T.D. I/We acknowledge and accept the duration of the Integrity Agreement, which shall be in the line with Article 1 of the enclosed Integrity Agreement.

I/We acknowledge that in the event of my/our failure to sign and accept the Integrity Agreement, while submitting the tender/bid, I.I.T.D shall have unqualified, absolute and unfettered right to disqualify the tender / bidder and reject the tender/bid is accordance with terms and conditions of the tender/bid.

Yours faithfully

(Duly authorized signatory of the Bidder)

INTEGRATY PACT e-TENDERING

I.I.T.D

To be signed by the bidder and same signatory competent / authorized to

sign the relevant contract on behalf of I.I.T.D.

INTEGRITY AGREEMENT

This Integrity Agreement is made at on this day of 20
BETWEEN
The Board of Governors, I.I.T. Delhi, Hauz Khas, New Delhi - 16 represented through Executive Engineer (E) IIT Delhi.
'Principal/Owner', which expression shall unless repugnant to the meaning or context hereof include its successors and permitted assigns)
AND (Name and Address
of the Individual/firm/Company) through(Hereinafter referred to as the (Details of duly authorized signatory) "Bidder/Contractor" and which expression shall unless repugnant to the meaning or context hereof include its successors and permitted assigns) Preamble
WHEREAS the Principal / Owner has floated the Tender (NIT No) (Hereinafter referred to as
"Tender/Bid") and intends to award, under laid down organizational procedure, contract for
(Name of work) hereinafter referred to as the "Contract". AND WHEREAS the Principal/Owner values full compliance with all relevant laws of the land,

C----NIL I----NIL O--- NIL

documents and Contract between the parties.

rules, regulations, economic use of resources and of fairness/transparency in its relation with its Bidder(s) and Contractor(s).AND WHEREAS to meet the purpose aforesaid both the parties have agreed to enter into this Integrity Agreement (hereinafter referred to as "Integrity Pact" or "Pact"), the terms and conditions of which shall also be read as integral part and parcel of the Tender/Bid

INTEGRATY PACT e-TENDERING I.I.T.D

Now, THEREFORE, in consideration of mutual covenants contained in this Pact, the parties hereby agree as follows and this Pact witnesses as under:

Article 1: Commitment of the Principal/Owner

- 1) The Principal/Owner commits itself to take all measures necessary to prevent corruption and to observe the following principles:
 - (a) No employee of the Principal/Owner, personally or through any of his/her family members, will in connection with the Tender, or the execution of the Contract, demand, take a promise for or accept, for self or third person, any material or immaterial benefit which the person is not legally entitled to.
 - (b) The Principal/Owner will, during the Tender process, treat all Bidder(s) with equity and reason. The Principal/Owner will, in particular, before and during the Tender process, provide to all Bidder(s) the same information and will not provide to any Bidder(s) confidential / additional information through which the Bidder(s) could obtain an advantage in relation to the Tender process or the Contract execution.
 - (c) The Principal/Owner shall endeavour to exclude from the Tender process any person, whose conduct in the past has been of biased nature.
- 2) If the Principal/Owner obtains information on the conduct of any of its employees which is a criminal offence under the Indian Penal code (IPC)/Prevention of Corruption Act, 1988 (PC Act) or is in violation of the principles herein mentioned or if there be a substantive suspicion in this regard, the Principal/Owner will inform the Chief Vigilance Officer and in addition can also initiate disciplinary actions as per its internal laid down policies and procedures.

Article 2: Commitment of the Bidder(s)/Contractor(s)

- It is required that each Bidder/Contractor (including their respective officers, employees and agents) adhere to the highest ethical standards, and report to the Government / Department all suspected acts of fraud or corruption or Coercion or Collusion of which it has knowledge or becomes aware, during the tendering process and throughout the negotiation or award of a contract.
- 2) The Bidder(s)/Contractor(s) commits himself to take all measures necessary to prevent corruption. He commits himself to observe the following principles during his participation in the Tender process and during the Contract execution:
 - a) The Bidder(s)/Contractor(s) will not, directly or through any other person or firm, offer, promise or give to any of the Principal/Owner's employees involved in the Tender process or execution of the Contract or to any third person any material or other benefit which he/she is not legally entitled to, in order to obtain in exchange any advantage of any kind whatsoever during the Tender process or during the execution of the Contract.
 - b) The Bidder(s)/Contractor(s) will not enter with other Bidder(s) into any undisclosed agreement or understanding, whether formal or informal. This applies in particular to prices, specifications, certifications, subsidiary contracts, submission or non-submission of bids or any other actions to restrict competitiveness or to cartelize in the bidding process.\

INTEGRATY PACT e-TENDERING

I.I.T.D

- c) The Bidder(s)/Contractor(s) will not commit any offence under the relevant IPC/PC Act. Further the Bidder(s)/Contract(s) will not use improperly, (for the purpose of competition or personal gain), or pass on to others, any information or documents provided by the Principal/Owner aspart of the business relationship, regarding plans, technical proposals and business details, including information contained or transmitted electronically.
- d) The Bidder(s)/Contractor(s) of foreign origin shall disclose the names and addresses of agents/representatives in India, if any. Similarly Bidder(s)/Contractor(s) of Indian Nationality shall disclose names and addresses of foreign agents/representatives, if any. Either the Indian agent on behalf of the foreign principal or the foreign principal directly could bid in a tender but not both. Further, in cases where an agent participate in a tender on behalf of one manufacturer, he shall not be allowed to quote on behalf of another manufacturer along with the first manufacturer in a subsequent/parallel tender for the same item.
- e) The Bidder(s)/Contractor(s) will, when presenting his bid, disclose any and all payments he has made, is committed to or intends to make to agents, brokers or any other intermediaries in connection with the award of the Contract.
- 3) The Bidder(s)/Contractor(s) will not instigate third persons to commit offences outlined above or be an accessory to such offences.
- 4) The Bidder(s)/Contractor(s) will not, directly or through any other person or firm indulge in fraudulent practice means a willful misrepresentation or omission of facts or submission of fake/forged documents in order to induce public official to act in reliance thereof, with the purpose of obtaining unjust advantage by or causing damage to justified interest of others and/or to influence the procurement process to the detriment of the Government interests.
- The Bidder(s)/Contractor(s) will not, directly or through any other person or firm use Coercive Practices (means the act of obtaining something, compelling an action, or influencing a decision through intimidation, threat or the use of force directly or indirectly, where potential or actual injury may befall upon a person, his/ her reputation or property to influence their participation in the tendering process).

Article 3: Consequences of Breach

Without prejudice to any rights that may be available to the Principal/Owner under law or the Contract or its established policies and laid down procedures, the Principal/Owner shall have the following rights in case of breach of this Integrity Pact by the Bidder(s)/Contractor(s) and the Bidder/ Contractor accepts and undertakes to respect and uphold the Principal/Owner's absolute right:

- If the Bidder(s)/Contractor(s), either before award or during execution of Contract has committed a transgression through a violation of Article 2 above or in any other form, such as to put his reliability or credibility in question, the Principal/Owner after giving 14 days' notice to the contractor shall have powers to disqualify the Bidder(s)/Contractor(s) from the Tender process or terminate/determine the Contract, if already executed or exclude the Bidder/Contractor from future contract award processes. The imposition and duration of the exclusion will be determined by the severity of transgression and determined by the Principal/Owner. Such exclusion may be forever or for a limited period as decided by the Principal/Owner.
- 2) **Forfeiture of EMD/Performance Guarantee/Security Deposit**: If the Principal/Owner has disqualified the Bidder(s) from the Tender process prior to the award of the Contract or terminated/determined the Contract or has accrued the right to terminate/determine the Contract according to Article 3(1), the Principal/Owner apart from exercising any legal rights that may

have accrued to the Principal/Owner, may in its considered opinion forfeit the entire amount of Earnest Money Deposit, Performance Guarantee and Security Deposit of the Bidder/Contractor.

3) **Criminal Liability**: If the Principal/Owner obtains knowledge of conduct of a Bidder or Contractor, or of an employee or a representative or an associate of a Bidder or Contractor which constitutes corruption within the meaning of IPC Act, or if the Principal/Owner has substantive suspicion in this regard, the Principal/Owner will inform the same to law enforcing agencies for further investigation.

Article 4: Previous Transgression

- 1) The Bidder declares that no previous transgressions occurred in the last 5 years with any other Company in any country confirming to the anticorruption approach or with Central Government or State Government or any other Central/State Public Sector Enterprises in India that could justify his exclusion from the Tender process.
- 2) If the Bidder makes incorrect statement on this subject, he can be disqualified from the Tender process or action can be taken for banning of business dealings/ holiday listing of the Bidder/Contractor as deemed fit by the Principal/ Owner.
- 3) If the Bidder/Contractor can prove that he has resorted / recouped the damage caused by him and has installed a suitable corruption prevention system, the Principal/Owner may, at its own discretion, revoke the exclusion prematurely.

Article 5: Equal Treatment of all Bidders/Contractors/Subcontractors

- The Bidder(s)/Contractor(s) undertake(s) to demand from all subcontractors a commitment in conformity with this Integrity Pact. The Bidder/Contractor shall be responsible for any violation(s) of the principles laid down in this agreement/Pact by any of its Sub-contractors/sub-vendors.
- 2) The Principal/Owner will enter into Pacts on identical terms as this one with all Bidders and Contractors.
- 3) The Principal/Owner will disqualify Bidders, who do not submit, the duly signed Pact between the Principal/Owner and the bidder, along with the Tender or violate its provisions at any stage of the Tender process, from the Tender process.

Article 6- Duration of the Pact

This Pact begins when both the parties have legally signed it. It expires for the Contractor/Vendor 09 Months after the completion of work under the contract or till the continuation of defect liability period, whichever is more and for all other bidders, till the Contract has been awarded.

If any claim is made/lodged during the time, the same shall be binding and continue to be valid despite the lapse of this Pacts as specified above, unless it is discharged/determined by the Competent Authority, I.I.T.D.

Article 7- Other Provisions

- 1) This Pact is subject to Indian Law, place of performance and jurisdiction is the Headquarters of the Division of the Principal/Owner, who has floated the Tender.
- 2) Changes and supplements need to be made in writing. Side agreements have not been made.
- 3) If the Contractor is a partnership or a consortium, this Pact must be signed by all the partners or by one or more partner holding power of attorney signed by all partners and consortium members. In case of a Company, the Pact must be signed by a representative duly authorized by board resolution.
- 4) Should one or several provisions of this Pact turn out to be invalid; the remainder of this Pact remains valid. In this case, the parties will strive to come to an agreement to their original intensions.

INTEGRATY PACT e-TENDERING

I.I.T.D

5) It is agreed term and condition that any dispute or difference arising between the parties with regard to the terms of this Integrity Agreement / Pact, any action taken by the Owner/Principal in accordance with this Integrity Agreement/ Pact or interpretation thereof shall not be subject to arbitration.

Article 8- LEGAL AND PRIOR RIGHTS

All rights and remedies of the parties hereto shall be in addition to all the other legal rights and remedies belonging to such parties under the Contract and/or law and the same shall be deemed to be cumulative and not alternative to such legal rights and remedies aforesaid. For the sake of brevity, both the Parties agree that this Integrity Pact will have precedence over the Tender/Contact documents with regard any of the provisions covered under this Integrity Pact.

IN WITNESS WHEREOF the parties have signed and executed this Integrity Pact at the place and date first above mentioned in the presence of following witnesses:

(For and on behalf of Principal/Owner)

(For and on behalf of Principal/Owner)
(For and on behalf of
Bidder/Contractor)
WITNESSES:
1
(signature, name and address)
2. (signature, name and address)
Place:

Date:

I.I.T. D

Form of Earnest Money Deposit Bank Guarantee Bond

	WHEREAS, contractor(Name of contractor) (hereinafter called "the contractor") has submitted his tender dated (date) for the construction of(name of work) (hereinafter called "the Tender")
	KNOW ALL PEOPLE by these presents that we
	(Name and division of Executive Engineer) (hereinafter called "the Engineer-in-Charge") in the sum of Rs
	SEALED with the Common Seal of the said Bank thisday of
(1)	If after tender opening the Contractor withdraws, his tender during the period of validity of tender (including extended validity of tender) specified in the Form of Tender;
(2)	If the contractor having been notified of the acceptance of his tender by the Engineer-in-Charge:
(a)	fails or refuses to execute the Form of Agreement in accordance with the Instructions to contractor, if required; OR
(b)	fails or refuses to furnish the Performance Guarantee, in accordance with the provisions of tender document and Instructions to contractor,
(c)	OR fails or refuses to start the work, in accordance with the provisions of the contract and Instructions to contractor,
(d)	OR fails or refuses to submit fresh Bank Guarantee of an equal amount of this Bank Guarantee, against Security Deposit after award of contract.
	We undertake to pay to the Engineer-in-Charge either up to the above amount or part thereof upon receipt of his first written demand, without the Engineer-in-Charge having to substantiates his demand, provided that in his demand the Engineer-in-Charge will note that the amount claimed by his is due to him owing to the occurrence of one or any of the above conditions, specifying the occurred condition or conditions.
	This Guarantee will remain in force up to and including the date*
	submission of tender as such deadline is stated in the Instructions to contractor or as it may be extended by the Engineer-in-Charge, notice of which extension(s) to the Bank is hereby waived. Any demand in respect of this Guarantee should reach the Bank not later than the above date.
	DATE
	SIGNATURE OF THE BANK WITNESSSEAL
	(SIGNATURE, NAME AND ADDRESS)
*Date	e to be worked out on the basis of validity period of 6 months from last date of receipt of tender.

C----NIL I----NIL O--- NIL EE (CD-I) AE (C)

PERFORMANCE GUARANTEE

- (i) The contractor shall submit an irrevocable Performance Guarantee of 5% (Five Percent) of the tendered amount in addition to other deposits mentioned elsewhere in the contract for his proper performance of the contract agreement, (not withstanding and/or without prejudice to any other provisions in the contract) within period specified in Schedule 'F' from the date of issue of letter of acceptance. This period can be further extended by the Engineer-in-Charge up to a maximum period as specified in schedule 'F' on written request of the contractor stating the reason for delays in procuring the Performance Guarantee, to the satisfaction of the Engineer-in-Charge. This guarantee shall be in the form of Cash (in case guarantee amount is less than Rs. 10,000/-) or Deposit at Call receipt of any scheduled bank/Banker's Cheque of any scheduled bank/Demand Draft of any scheduled bank/Pay Order of any scheduled bank (in case guarantee amount is less than Rs. 1,00,000/-) or Government Securities or Fixed Deposit Receipts or Guarantee Bonds of any Scheduled Bank or the State Bank of India in accordance with the form annexed hereto. In case a fixed deposit receipt of any Bank is furnished by the contractor to the Government as part of the performance guarantee and the Bank is unable to make payment against the said fixed deposit receipt, the loss caused thereby shall fall on the contractor and the contractor shall forthwith on demand furnish additional security to the Government to make good the deficit.
- (ii) The Performance Guarantee shall be initially valid up to the stipulated date of completion plus 60 Days beyond that. In case the time for completion of work gets enlarged, the contractor shall get the validity of Performance Guarantee extended to cover such enlarged time for completion of work. After recording of the completion certificate for the work by the competent authority, the performance guarantee shall be returned to the contractor, without any interest.
- (iii) The Engineer-in-Charge shall not make a claim under the performance guarantee except for amounts to which the BOG is entitled under the contract (not withstanding and/or without prejudice to any other provisions in the contract agreement) in the event of:
- (a) Failure by the contractor to extend the validity of the Performance Guarantee as described herein above, in which event the Engineer-in-Charge may claim the full amount of the Performance Guarantee.
- (b) Failure by the contractor to pay BOG any amount due, either as agreed by the contractor or determined under any of the Clauses/Conditions of the agreement, within 30 days of the service of notice to this effect by Engineer-in-Charge.
- (iv). In the event of the contract being determined or rescinded under provision of any of the Clause/Condition of the agreement, the performance guarantee shall stand forfeited in full and shall be absolutely at the disposal of the BOG.

1. Name & Address of the bidder

FORM "F"

STRUCTURE & ORGANISATION

2.	Telephone no./ Telex no./ Fax no.			
3.	Legal status of the bidder (attach copies of original document defining the legal status)			
a.	An Individual			
b.	A proprietary firm			
c.	A firm in partnership			
d.	A limited company or Corporation			
4.	Particulars of registration with various Government Bodies (attach attested photocopy) Organization/ Place of registration and Registration No.			
	1.			
	2.			
	3.			
5.	Name and tiles of Directors & Officers with designation to			
	be concerned with this work			
	!			
6.	Designation of individuals authorized to act for the organization			
7.	Has the bidder or any constituent partner in case of partnership firm, ever abandoned the			
	awarded work before its completion?			
	If so, give name of the project and reasons for abandonment			
	!			
8.	Has the bidder or any constituent partner in case of partnership			
	firm, ever been debarred/ blacklisted for tendering in any organization			

C-----NIL I----NIL O--- NIL EE (CD-I) AE (C)

Signature of Bidder(S)

ANNEXURE-I COMPLIANCE SHEET

TECHNICAL SPECIFICATION:

S.No.	Technical Bid Requirement As per Tender Notice & NIT & IITD form 8	Compliance Y/N
1	Demand Draft/Pay order or Banker`s Cheque /Deposit at Call Receipt/FDR of any Scheduled Bank against EMD.	
2	Enlistment order of contractor.	
3	Certificate of work experience.	
4	Certificate of Registration for GST and acknowledgement of up to date filed return of GST.	
5	Affidavit on Rs.100/- Non judicial Stamp as per Notice Inviting Tender	
	Condition 1.3 at page 8 of NIT. (Stamp Paper shall be purchased/ notarized	
	between date of publishing and last date of submission of bids beside this	
	NIT/Tender ID and name of work must be mentioned on the affidavit).	
6	Acceptance to execute INTEGRITY PACT.	
7	Undertaking as per page-5/ Sl. No. 20' on firm's letter head. "the physical EMD shall be deposited by me / us with the Authority inviting	
	the tender, in case I / we become the lowest tenderer, within a week of the	
	opening of financial bid, otherwise, department may reject the tender and also take action to debar me / us from tendering in any form in IIT Delhi"	
8	ESI & EPF registration.	
9	FORM "F" (Duly filled with all required details).	
10	Annexure-1 (Dully Filled & signed by the bidders)	
11	Annexure 2 (Dully Filled & signed by the bidders)	
12	Annexure 3 (Dully Filled & signed by the bidders)	
13	In case of Partnership firm if all the papers of tender not signed by all the partners than a power of attorney authorizing the person who has signed the tender paper must be uploaded with the tender documents.	
14	Any other documents given in NIT	
15	BOQ	

I have also enclosed all relevant documents in support of my claims, (as above) in the following pages.

	Signature of Bidder
Name:	
Designation:	
Organization Nan	ne:
Contact No. :	

ANNEXURE-II

<< Organization Letter Head >> DECLARATION SHEET

We,	hereby certify that all the information and data
	is tender specification are true and complete to the best of ication, conditions and stipulations in details and agree to ecification.
This is certified that our organization has been	registered as per Tender Notice & NIT & IITD form
_	tion meets all the conditions of eligibility criteria laid down
in this tender document.	
We, further specifically certify that our	NAME & ADDRESS of the Vendor/ Manufacturer / Agent
organization has not been Black Listed/De	
Listed or put to any Holiday by any	
Institutional Agency/ Govt. Department/	
Public Sector	
Undertaking in the last three years.	
1. Phone	
2. Fax	
3. E-mail	
4. Contact Person Name	
5. Mobile Number	
6. GST Number	
7. PAN Number	
8.(In case of on-line payment of Tender Fees)	
UTR No. (For Tender Fee)	
9.(In case of on-line payment of EMD)	
UTR No. (For EMD)	

(Signature of the Tenderer)

Name:

Seal of the Company

Annexure-III

List of Govt. Organization/Deptt.

Notice & NIT & IITD form 8					
Name of the organization	Name of Contact Person	Contact No.			
	+				

Signature of Bidder
Name:
Designation:
Organization Name:
Contact No. :

I.I.T.D – 7/8 e-TENDERING

I.I.T.D

PART-B

INDIAN INSTITUTE OF TECHNOLOGY DELHI HAUZ KHAS, NEW DELHI - 110016 Item Rate Tender & Contract for Composite Work

Tender for the work of: Comprehensive Maintenance of Civil work, Horticulture, Public Health Work, Service of Housekeeping and Round the clock O & M services for public health work at Sonipat Campus of IIT Delhi for the year 2025-2026.

		•	•	iaer notice							
				n presence						tender	notice
in the of	fice of l	 D.R. (§	Store)								
Issued to	o					 	 	 	 		
Signatur	e of off	icer iss	suing th	e documen	ts.	 	 	 	 		
Designa	tion					 	 	 	 		
Date of l	Issue				• • • •						

TENDER

I/We have read and examined the notice inviting tender, schedule, A, B, C, D, E & F Specifications applicable, Drawings & Designs, General Rules and Directions, Conditions of Contract, clauses of contract, Special conditions, Schedule of Rate & other documents, and Rules referred to in the conditions of contract and all other contents in the tender document for the work.

I/We hereby tender for the execution of the work specified for the The Board of Governors, I.I.T. Delhi, Hauz Khas, New Delhi - 16 within the time specified in Schedule 'F' viz., schedule of quantities and in accordance in all respect with the specifications, designs, drawing and instructions in writing referred to in Rule-1 of General Rules and Directions and in Clause 11 of the Conditions of contract and with such materials as are provided for, by, and in respect of accordance with, such conditions so far as applicable.

We agree to keep the tender open for **Seventy-Five** (75) days from last date of submission of bid.

A sum of **as per tender notice** is hereby forwarded in Banker Cheque or Demand Draft or Fixed Deposit receipt of a schedule bank drawn in favour of IIT Delhi as earnest money. If I/We, fail to furnish the prescribed performance guarantee within prescribed period. I/We agree that the said The Board of Governors,

I.I.T. Delhi, Hauz Khas, New Delhi - 16 or his successors, in office shall without prejudice to any other right or remedy, be at liberty to forfeit the said earnest money absolutely. Further, if I/We fail to commence work as specified, I/We agree that The Board of Governors, I.I.T. Delhi, Hauz Khas, New Delhi - 16 or the successors in office shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the said earnest money and the performance guarantee absolutely, otherwise the said earnest money shall be retained by him towards security deposit to execute all the works referred to in the tender documents upon the terms and conditions contained or referred to those in excess of that limit at the rates to be determined in accordance with the provision contained in Clause 12.2 and 12.5 of the tender form. Further, I/We agree that in case of forfeiture of Earnest Money & Performance Guarantee as aforesaid. I/We shall be debarred for participation in the re-tendering process of the work.

I.I.T.D – 7/8 e-TENDERING	I.I.T.D
---------------------------	---------

I/We undertake and confirm that eligible similar work(s) has/have not been got executed through another contractor on back to back basis. Further that, if such a violation comes to the notice of Department, then I/We shall be debarred for tendering in I.I.T.D in future forever. Also, if such a violation comes to the notice of Department before date of start of work, the Engineer-in-Charge shall be free to forfeit the entire amount of Earnest Money Deposit/Performance Guarantee.

I/We hereby declare that I/We shall treat the tender documents drawings and other records connected with the work as secret/confidential documents and shall not communicate information/derived there from to any person other than a person to whom I/We am/are authorized to communicate the same or use the information in any manner prejudicial to the safety of the State.

Dated:	
	Signature of Contractor
Witness:	Postal Address
Address:	
Occupation:	

I.I.T.D

ACCEPTANCE

The above tender (as modified by you as provided in the letters mentioned hereunder) is
accepted by me for an on behalf of The Board of Governors, I.I.T. Delhi, Hauz Khas, New
Delhi - 16 for a sum of
(Rupees).
The letters referred to below shall form part of this contract agreement: -
(a)
(b)
(c)
For & on behalf of Board of Governors, IIT Delhi Signature
Dated:
Designation

PROFORMA OF SCHEDULES I.I.T.D

SCHEDULES (A to F)

(For Comprehensive Maintenance of Civil work, Horticulture, Public Health Work, Service of Housekeeping and Round the clock O & M services for public health work at Sonipat Campus of IIT Delhi for the year 2025-2026)

SCHEDULE 'A'

Schedule of quantities for Civil work, Horticulture, Public Health Work, Service of Housekeeping and Round the clock O & M services for public health work as attached.

SCHEDULE 'B'

Schedule of materials to be issued to the contractor.

S.No.	Description of item	Quantity	Rates in figures &	Place of		
			words at which the	issue		
			material will be			
			charged to the			
			contractor			
1	2	3	4	5		
	NIL					

SCHEDULE 'C'

Tools and plants to be hired to the contractor.

	NIL					
Ī	1	2	3	4		
	S.No.	Description	Hire charges per day	Place of Issue		

SCHEDULE 'D'

Extra schedule for specific requirement/document for the work, if any.

Nil.

SCHEDULE 'E'

Reference to General Conditions of : contract

GCC for Maintenance work 2023 for CPWD works along with correction slips/ amendments issued up to last

date of submission of bid.

Name of Work : Comprehensive Maintenance of Civil

work, Horticulture, Public Health Work, Service of Housekeeping and Round the clock O & M services for public health work at Sonipat Campus of IIT Delhi for

the year 2025-2026.

Estimated cost of work: : **Rs. 2,90,36,106/-**

Earnest Money: : **Rs. 5,80,722**/-

Performance Guarantee : 5% of tendered Value

Security deposit : 2.5 % of tendered value

SCHEDULE 'F'

GENERAL RULES & DIRECTIONS:

1. Officer inviting tender : Executive Engineer [CD-I]

2.Maximum percentage for quantity of items of work to be executed beyond which rates are to be determined in accordance with

Clauses 12.2 & 12.5

Clause 12

Definitions:

2(i) Engineer-in-Charge : Executive Engineer [CD-I]

2(ii) Accepting Authority : Institute Engineer

2(iii) Percentage on cost of materials and : 15%

Labour to cover all overheads and

profits:

2(iv) Standard Schedule of Rates: : DSR 2023 for Civil works with

correction factor 0.973 on DSR items, cost index @ 3% & Non-schedule items on Market Rate and with upto-date correction slip on date of submission of

bid.

2(v) Department : Works department at I.I.T Delhi.

2(vi) Standard IITD Form & CPWD GCC for Maintenance work 2023, modified & corrected up to last date of submission of bid

Clause 1

(i) Time allowed for submission of : 15 days

Performance Guarantee from the date of issue of letter of

acceptance

(ii) Maximum allowable : 5 days

extension with late fee @ 0.1 % per day of Performance guarantee amount beyond the period provided in (i) above,

Clause 2

Authority for fixing compensation under : Institute Engineer

Delay:

Clause 5

Number of days from the date of issue : 10 days or earlier as per direction of

of letter of acceptance for reckoning date of start: Engineer-in-charge

MILE STONE CHART

Sl. No.	Description of mile stone (financial terms)	Period for completion from date of start in days/months	Withheld amount for non- achievement of mile stone.
1	Nil		
2	Nil		
3	Nil		
4	Nil		

Allowed for execution of work : 12 Months

Authority to decide:

(i) Extension of Time : Institute Engineer(ii) Rescheduling of mile stones : Institute Engineer

(iii) Shifting of Date of start in case of

Delay in handing over of site : Institute Engineer

Clause (6) : Applicable (Computerized MB)

:

Clause 7

Gross work to be done together with net payment /adjustment of advances for material collected, if any, since the last such payment for being eligible to interim payment: Minimum Rs. 25.00 Lakhs

Clause -7A : As per Institute Policy

No running account bill shall be paid for the work till the applicable labour licences, registration with EPFO, ESIC and BOCW Welfare Board, whatever applicable are submitted by the contractor to the Engineer-in-Charge.

Clause 10A

List of testing equipment to be provided by : **Not Applicable**

the contractor at site lab

Clause 10B : Not Applicable

Clause 10C

Component of labour expressed as percent of value of work:.

Work	Item No.	Material	Labour
Civil work	1 to 104	75	25
Horticulture & Landscaping	105 to 106	75	25
Civil Maintenance work	107.01 to 107.10	-	100
Supply of material for civil work	108.01 to 108.16	100	-
Housekeeping services	109.01 to 109.5	-	100
Housekeeping machine/equipment's	110.01 to 110.04	100	-
Housekeeping chemical & consumable	111.01to 111.47	100	-

Note:- Above % (percent) shall be 85% of component defined.

Clause 10CA : Not Applicable

S. No.	Material Covered under this clause	Nearest Materials (other than cement, reinforcement bars and the structural steel) for which All India Wholesale Price Index to be followed	Base Price of all Materials covered under clause 10 CA* (July 2022)
1.	Cement		
2.	Cement	Not Applic	able
3.	Reinforcement bars		
4.	Structural steel		

Clause 10CC

Clause 10 CC to be applicable in contracts with stipulated period of completion exceeding the period shown in next column

Not Applicable

Clause 11

Specifications to be followed for : execution of work

CPWD specifications 2019 Vol I and Vol II and upto the last date of bid submission/uploading of tender.

Detailed nomenclature of items & specifications for market rate items as per Engineer-in-charge

Clause 12

Type of work Maintenance work.

12.2 & 12.5 Deviation limit beyond : 100%

which clauses

12.2 & 12.5 shall apply for building work

C-----NIL I----NIL O--- NIL EE (CD-I) AE (C)

12.5 (I) Deviation Limit beyond which clauses: 100%
12.2 & 12.5 shall applicable
for foundation work (Except items
mentioned in earthwork subhead of DSR
and related items)

12.5 (II) Deviation Limit for Items in earth work subhead of DSR and related items

Clause 16

Competent Authority for deciding reduced rates : Institute Engineer

Clause 18

List of mandatory machinery, tools & : As per requirement plants to be deployed by the contractor at site

Clause 25

Constitution of Dispute Redressal Committee (DRC)					
Chairman					
Member	NIL				
Member					

Note: The above constitution of Dispute Redressal Committee is subject to change, for which necessary notification shall be issued by the competent authority of the department, if required.

Clause 32

Requirement of Technical Staff(s) & Recovery Rate

Cost of Work (Rs. In Crore)	Requirement Qualification	Number (Of major + minor component)	Minimum Experience (Years)	Designation Technical Staff	Rate at which recovery shall be made from the Contractor in the event of not fulfilling provision of clause 32
More than 1.5 Cr. to 5 Cr.	Graduate Engineer or Diploma Engineer	2 (1 Civil Engineer) + (1Horticulturist)	or 5 Respectively	Project planning/ quality/ Site/billing Engineer	Rs. 15,000/- per month per person

Assistant Engineers retired from Government services that are holding Diploma will be treated at par with Graduate Engineers.

Diploma Holder with minimum 10 years relevant experience with a reputed construction company can be treated at par with graduate Engineers for the purpose of such deployment subject to the condition that such diploma holders should not exceed 50 % of requirement of degree Engineer.

Clause 38

i)	Schedule/statement for determining theoretical quantity of cement & bitumen on the basis of Delhi Schedule of Rates 2021with up to date correction printed by C.P.W.D.				
ii)	Variations permissible on theoretical quantities				
a)	Cement:				
	For works with estimated cost put to tender not more	3% plus/minus. (Three			
	than Rs.5 lakh.	percent)			
	For works with estimated cost put to tender more than	2% plus/minus. (Two			
	Rs.5 lakh	percent)			
b)	Bitumen all works.	2.5% plus & only & nil on			
		minus side			
c)	Steel Reinforcement and structural steel sections for	2% plus/minus (Two			
	each diameter, section and category	percent)			
d)	All other materials				
e)	Schedule for determining theoretical consumption of Brick work on the basis of DSR				
	2021				

SPECIAL CONDITIONS

- 1.0 Non-Judicial stamp paper worth Rs. 100/- (Hundred Rupees only) will be submitted by the contractor which will have to be signed as token of acceptance.
- 2.0 No T & P would be supplied by the Institute and contractor will have to make his own arrangement.
- 3.0 The contractors are advised to get acquitted with the proposed work including specifications & its site and additional conditions carefully before quoting. No claim of any sort shall be entertained or account of any site conditions and ignorance of specifications & additional conditions. The work shall be carried out as per the availability of site.
- 4.0 The work shall be carried out as per CPWD specifications for civil and electrical work with up to date correction slips unless otherwise specified in the nomenclature of individual item or in the specification, additional conditions where specifications are silent, the decision of Engineer-in-Charge shall be final and binding on contractor.
- The rates quoted by the contractor shall be taken as net and nothing extra shall be paid on any account i.e Royalty, Cartage, GST & stacking of material required at places etc. The rates for different items of work shall apply for Heights & Depths, Leads & Lifts unless otherwise specified in the agreement or specifications applicable in the agreement.
- Any damage done by the contractor to any existing item / any part of the building during the course of execution of work shall be made good by at his own cost.
- 7.0 Articles manufactured by the reputed firms as per approved make list and as approved by Engineer-in-charge shall only be used at work.
- 8.0 The sample of material required in the work brought at site shall be submitted prior technical specification of individual item and got approval of material from Engineer –in-Charge before use in execution of work.
- 9.0 The sample of material required for Testing shall be provided at free of cost by the contractor. All other expenditure to be incurred for taking sample, conveyance, packing and testing charges etc. shall be borne by the contractor.
- 10.0 The contractor shall submit a detailed program of work within **10 days** of the date of award of work. The Engineer in- Charge can modify the program and the contractors have to work accordingly.
- 11.0 The contractor shall make his own arrangement for getting the permission with respect to trucks from the Traffic Police.
- 12.0 No payment shall be made to contractor for any damage caused by the rain, snowfall or any other natural causes whatsoever during the execution of work.
- 13.0 Some restrictions may be imposed by the security staff of IIT Delhi etc. on the working and or movement of labour & material. No labour camp/ huts shall be allowed in Sonipat campus of IIT Delhi. The contractor shall make his own arrangement for labour huts outside the campus. However, construction of cement godown and Chowkidar's hut in the Campus shall be permitted. The contractor shall be bound to follow all such restrictions/ instructions, and nothing shall be payable on this account.
- 14.0 The contractor shall be fully responsible for the safe custody of the material issued or brought at site by him for doing the work.
- 15.0 The Malba / Garbage generated at site due to construction activities shall be removed from the site immediately & shall be disposed off by the contractor to the approved dumping site of MCD and all statutory approvals from local bodies shall be a sole responsibility of contractor.

- 16.0 The contractor shall clean the site thoroughly of scaffolding materials, rubbish, equipment's left out of his work & dress the site around the building to the complete satisfaction of the Engineer-in-Charge before the work is treated as completed.
- 17.0 Contractor has to quote against the item of schedule of credit of material. The contractor cannot quote either minus rate or Zero rate for these items.
- 18.0 Income tax and other taxes as applicable shall be deducted from the bills of contractor.
- 19.0 1% labour cess or as applicable will be deducted from the bills of contractor.
- Water charges @1% and Electricity charges @0.50% of gross work done shall be deducted from bills of contractor if electricity and water provided by IIT Delhi.
- 21.0 Agency has to take proper safety major during the execution of work.
- 22.0 GCC form 7/8 shall form part of NIT and the bidder shall go through GCC 2023 CPWD before quoting rates and the same shall be deemed to be accepted by bidder if he participates in the tender.
- 23.0 ESI & EPF shall be reimbursed as per norms on production of original receipt of ESI & EPF from contractor specific to this work.
- 24.0 The contractor shall submit the program of execution of work as per clause 5 of GCC of IIT form 7/8 of NIT including list of workers to be deployed by contractor for this work.
- 25.0 Contractor shall be responsible for keeping site free of any kind of mosquito breeding. If it is found that breeding is taking place the entire responsibility shall be of contractor to bear challan etc. done by local bodies.
- 26.0 GST shall considered as inclusive in quoted rate of agency.
- 27. **Specialized Work:**
- 27.1 The following works are considered as specialized work.

(a). Housekeeping

- The above specialized work shall be carried by specialized agencies/ agency on their own if they have experience of (a) 03 similar work of 40% value of specialized work component of Tendered amount.
 - (b) 02 similar work of 60% value of specialized work component of Tendered amount.
 - (c) 01 similar work of 80% value of specialized work component of Tendered amount.
- 28. Security Deposit shall be deducted from each running bill and final bill to the extent of 5% of the gross amount payable. The security deposit shall be released only after the work is complete in all respect i.e. Wages, EPF & ESI, Bonus etc. are fully cleared.
- 29. The rates quoted by the tenderer, shall be firm and inclusive of all taxes (including works GST & labour cess), duties, levies, etc. and all charges for packing forwarding, insurance, freight and delivery, installation, testing and commissioning etc. at site including temporary construction of storage, risks overhead charges, general liabilities/obligations.
- 30. The successful tenderer shall at all times indemnify the department, consequent on this works contract. The successful tenderer shall be liable, in accordance with the Indian Law and Regulations for any accident occurring due to any cause and the contractor shall be responsible for any accident or damage incurred or claims arising there from during the period of operation and maintenance under the supervision of the successful tenderer. The successful tenderer shall take necessary actions in this regard. No extra payment would be made to the successful tenderer on account of the above.

- 31. Institute has a policy against sexual harassment and is committed to providing an environment free from sexual harassment of women at the workplace. The contractor shall have to abide by the policy of the Institute with due diligence. Any violation on the part of the contractor shall be dealt with by the extant rules of the Institute.
- 32. That the Engineer-in-charge or any other person authorized by him shall be at liberty to carry out surprise checks on the persons so deployed by the contractor to ensure that persons deployed by him are doing their duties.
- 33. That the contractor shall particularly abide by the provisions of Minimum Wages Act, 1948. Minimum wages shall be paid by the Agency / Contractor at the rate fixed by Central Govt. from time to time. Arrears, if due as result of increase in minimum wages would be reimbursed to the contractor on submission of proof of actual payment to the worker. In case of half yearly increase in Minimum wages by the Central Govt., the contractor will submit copy of gazette notification to the Institute and the same may be considered by the Institute. The contractor shall take all reasonable precautions to prevent any unlawful, riotous or disorderly conduct or acts of his employees so deployed.
- 34. The Work is to be carried out for stipulated **period of 12 Months** and may be extended for further as desired by Engineer-in-charge.
- 35. Total number of manpower is fixed. However, the Institute can increase or decrease the manpower as per requirement in case there is exigencies. The increase / decrease in manpower would accordingly affect the billing on pro-rata basis.
- 36. That the contractor shall be required to maintain a permanent attendance register in addition to Biometric Attendance at Sonipat Campus premises which shall be open for inspection and checking by the authorized officers Sonipat Campus of IIT Delhi.
- 37. That the contractor shall make the payment of wages, etc. to persons so deployed monthly basis through Bank Transfer / electronic mode on or before 7th day of every month. Wages shall include bonus @ 8.33% of daily wage [as admissible] of the worker multiplied by number of days' work actually performed by the worker in a particular month, which shall also be shown separately on the wage sheet of the worker.
- 38. A consolidated wage sheet containing the names of all workers so deployed by the contractor duly signed / acknowledged by the workers after disbursal of wages to be submitted to the Engineer-in-charge every month. Proof of disbursal of wages to be submitted before claiming bill. The wage sheet shall contain mandatory fields as per following: [1] Sr. No., [2] Name of the worker, [3] Actual days of duty performed, [4] Total wages, [5] Bonus amount, [6] EPF contribution [as applicable], [7] ESI Contribution [as applicable], [8] Total deductions, [9] Net wages received / disbursed, [10] signature of the worker.
- 39. In case of delay of payment of wages beyond 07 days as specified, IIT Delhi shall arrange for payment to the workers at the risk & cost of the contractor. The decision of the Engineer in-charge in this regard shall be full & final and binding upon the contractor.
- 40. Attendance comparative sheet shall be prepared by the contractor and to be submitted to the Engineer-in-charge after completion of every month as per duty chart, desired days of duty of a particular worker allowing weekly off and actual days of duty performed by the said worker.
- 41. It would be the responsibility of contractor to arrange all permission/ approvals from all local bodies/statutory bodies & nothing extra shall be paid on account of this by the Institute.
- 42. The Agency/ firm shall be required to frame & work as per SOP (Standard Operating Procedure) Which shall be submitted to Institute after award of work and agency/firm shall strictly follow it.
- 43. The Contractor shall maintain in a readily accessible place first aid appliances including adequate supply of sterilized dressings and cotton wool.
- 44. An adequate insurance coverage shall be arranged by the contractor for all employees/workmen against

- accident & the Institute shall not be responsible for any liability arising out of any accident / injury caused to the employees/workmen while executing the work.
- 45. Recovery of the absenteeism for item of manpower engaged will be done as per basic rate + bonus + contractor profit + GST@18% + Labour Cess @ 1% + penalty Rs.50/- per day per person ± tendered cost above/below.
- 46. Penalties shall be imposed on machines after 48hrs of breakdown period and agency shall make sure that machines are made operational within break down period of 48hrs.
 - (a) Battery operated Ride on Scrubber Drier :- Rs. 700/- Per day per machine
 - (b) Back pack Vacuum Cleaner :- Rs. 50/- Per day per machine
 - (c) Single Disc Scrubber :-. Rs. 50/- Per day per machine.
 - (d) Heavy Duty High pressure Jet Washer :- Rs. 150/- Per day per machine.

Minimum wages for various type of Manpower Requirement

The detail of minimum wages of manpower to be engaged for above works mentioned as:

S.	Description	Basic Rate per	Bonus @ 8.33%	Total Rs.
No.		day	on Basic Rate	Per day
		(In Rs.)	(In Rs.)	(In Rs.)
(A)	Up Keeping of Maintenance Work			
1.	Supervisor (Civil)	868	=	868.00
2.	Mason	739	61.56	800.56
3.	Carpenter	739	61.56	800.56
4.	Plumber	739	61.56	800.56
5.	Pump Operator (PH)	614	51.15	665.15
6.	Painter	614	51.15	665.15
7.	Welder	614	51.15	665.15
8.	Sewerman	614	51.15	665.15
9.	Helper/ Beldar	526	43.82	569.82
10.	Mali	526	43.82	569.82
(B)	Housekeeping Services			
1.	Manager	992	-	992.00
2.	Helpdesk Executive (HK)	868	-	868.00
3.	HK Worker	526	43.82	569.82
4.	Waste collector/ HK Staff	526	43.82	569.82

In the event of an increase in minimum wages, the same shall be reimbursed on actual basis including effect of GST if any. Minimum wages taken as per circular F.No.1/27(3)/2024-LS-II, dt. 25/09/2024 for Sonipat city area under category -C.

FORM OF WATER PROOFING WORKS GUARANTEE BOND ON STAMP PAPER

This thousand	agreement	made	this	day	of	two
			lled the Guaranto		art) and the	
datedthe contract	made between	the Guaranton lertook to rend	y to the contract of the one part a der the Buildings	nd Govt. of the	other part, v	whereby
remain water		years to be re	a guarantee to the			
shall replace other defect the Enginee from the dat failing which Guarantor's	e at his risk and complete being found he so rein- Charge and e of issuing notice the the work shall cost and risk and	cost such mem shall render the shall commen to the Enging be got done din the latter of the such that the same tha	tor shall make g bers as may be da building waterprice the works of sineer-in-Charge ca by the Departme case the decision be final and binding	amaged by water roof at his cost of such rectification alling upon him and by some oth of the Engineer	er and in case to the satisfa n within sev to rectify the ner contracto	e of any action of en days e defects or at the
Guarantor w otherwise w performance damage and	vill indemnify pri hich may be incu e and observance	ncipal and his arred by him by of this supple by the Govern	aterproofing or co successors agains reason of any de emental agreement ment the decisio	st all loss, dama fault on the par nt. As to the an	nge, cost, exp t of the Guar nount of loss	pense or cantor in s and/or
In witness of Obligor	whereof of these	presents have	e been executed	by the		
and	For and		the BOG IIT Del			
SIGNED, Sopresence of 2.	EALED and delived.	vered by OBLI	GOR in			
SIGNED fo 1. 2.	r and on behalf of	f BOG IIT Del	hi by	in the	presence of-	
	ed by Contractor	/EE(CD-I)				

LIST OF APPROVED MAKES FOR CIVIL & ELECTRICAL WORKS

A:- Civil Items

S. No.	Description	Approved Makes
	EWC seat covers	HINDWARE/ PARRYWARE/ CERA/
1		KEROVIT
2	C.P brass fittings/ Accessories	JAQUAR/ MARC/ KOHLAR /KEROVIT
3	PVC Seat Cover	PRAYAG/ POLYTUF/SHAKTI/ PEARL
4	PVC Fittings/ Accessories	PRAYAG/ PRIMA/SHAKTI/ PEARL
_	Cement (Grey) OPC/ PPC Grade-43	ACC/ L&T/J.K/ BIRLA/ULTRA TECH/
5	•	VIKRAM
6	Cement(White)	J.K/ BIRLA
	Reinforcement Steel	PRIMARY MANUFACTURERS APPROVED
7		BY MINISTRY OF STEEL/ SECONDARY
'		MANUFACTURERS HAVING VALID BIS
		LICENSE (to be as per latest BIS provisions)
	Structural Steel	PRIMARY MANUFACTURERS APPROVED
8		BY MINISTRY OF STEEL/ SECONDARY
0		MANUFACTURERS HAVING VALID BIS
		LICENSE (to be as per latest BIS provisions)
9	Stainless Steel (Grade 304)	JINDAL/ SAIL/ SALEM
10	Bricks	COMMERCIALLY AVAILABLE OR
		REQUIRED STRENGTH
11	Aluminium Sections	HINDALCO/ JINDAL/ MAHAVIR
12	Flush doors	CENTURY/ MERINO/ DURO BOARD/
		GREEN
13	Laminates	GREENLAM/ DURO/ ARCHID/ MERINO/
		CENTURY
14	Glass	SAINT GOBAIN/ MODI FLOAT/ ASAHI
		FLOAT
15	Ceramic Glazed tiles/ Border tiles	1ST QUALITY KAJARIA/ NITCO/ JOHNSON/
1.0	V'(:C' - 1/T':1	ORIENT/ SOMANY
16	Vitrified Tiles	JOHNSON/ KAJARIA/ ORIENT/ SOMANY HINDUSTAN TILES/ SWASTIK/ DALAL
17	Interlocking Precast paver blocks/ Kerb Stone	HINDUSTAN TILES/ SWASTIK/ DALAL
18	Stainless Steel Hinges	JOLLY/ GARG/ AMIT/ ASJ/ SUPREME
19	Stainless Steel Hillges Stainless Steel Nuts/ Bolts/ Screws	KUNDAN/ PUJA/ ATUL/ GKW
19	Paint/ primer/ oil bound distemper/	1ST QUALITY PAINTS OF ASIAN/ BERGER/
20	Acrylic paint/ plastic paint	NEROLAC/ SHALIMAR /DULUX
	Water Proof Cement Paint/ Exterior Paint	1ST QUALITY PAINTS OF ASIAN PAINTS/
21	mater 11001 Cement I amy Exterior Failit	BERGER/ NEROLAC/ SHALIMAR /DULUX
	Sanitaryware (Vitreous China) (European	HINDWARE/ PARRYWARE/ CERA/
22	Seats, Urinals, Wash Basins, etc.)	KEROVIT
	G.I Pipes	TATA / JINDAL(HISSAR)/ BHUSHAN/ APL
23		APPOLO
24	G.I Fittings	UNIK/ ZOLOTO/ AM
25	Stainless Steel Sink	NEELKANTH/ JAINA/ KINGSTON (COBRA)
	Commercial Board/ PLY	MERINO/ DURO/ GREEN/ CENTURY/ KIT
26		(SWASTIK)
27	CI Pipes/ Fittings	RIF/ NECO/ BENGAL IRON WORKS/ BC/
27		SKF
20	CI Pipes "Class LA"	NICO/ KESORAM/ ELECTRO STEEL/
28		KAPILANSH
29	Floor Spring	DORMA/ GODREJ/ HAFELE/ GEZE/ OZONE
20	Door Closer	SANDHU/ HARDWIN/DORMA/ GODREJ/
30		HAFELE/ GEZE/ OZONE

31	Mirror	ATUL/ MOIGUARD / SAINT GOBAIN/
-	Westerd Direct	AASHI NISTA (MAC/MARVEL DÉCOR/SARIT
32	Vertical Blinds	VISTA/ MAC/ MARVEL DÉCOR/ SAINT GOBAIN/DECK DÉCOR
33	False Ceiling	ARMSTRONG/ SAINT GOBAIN/ META WORTH
34	Water proofing compound	SIKA/ FOSROC/ PIDILITE/ ASIAN/BASF/CICO
35	Particle Board	NOVA PAN/ BHUTAN BOARD/ ECO BOARD
36	Adhesive	FEVICOL/ VAMICOL/ DUNLOP/ VAM
30		ORGANIC / kajariya
37	Tile Adhesive	PIDILITE/ FERROUSCRETE/ BALLENDURA/
38	Wall Putty	CICO BIRLA /JK/ SARA
	Epoxy Grout	BALLENDURA / KERAKOLL/
39	Zpony orone	FERROUSCRETE
40	PVC Water storage tank (ISI marked)	SINTEX/ UNI PLAST/ POLYWELL
41	PVC insulated Water storage tank Heavy	SINTEX/ UNIPLAST/ POLYWELL/ EURO
41	Duty 4/5 layer	
42	Brass Ball Valve/ Gate Valve/ Float	ZOLOTO/ AM/ LEADER/ SANT
	Valve / Butterfly valve	
43	Aluminium Door fittings	CLASSIC/ EVEREST/ ARGENT
44	Brass Bib/ Stop cock	AGI/ ELITE/ SHAKTI/ SANT/ LEADER/ PRIMA
45	Thermoplastic paint	CBM/ CMS/ S.N. INDUSTRIES
46	Plaster of Paris Putty	ADHASHREE/ SHREE RAM/ J.K/ BIRLA
	RCC Pipe	LAKSHMI/ SOOD & SOOD/ JAIN &Co./
47	Recripe	DIWAN SPUN PIPES
48	PVC Pipe	PRAKASH/ PRINCE/ SUPREME
49	Sandwich Roof Panel (Puff Panel)	KAKTUS/ ZEP/ E- PACK/ LLOYED
50	WPC Board and MPC Board	FLORESTA, ECOSTE, RAJ SHREE
51	WPC Door Frame	FLORESTA, ECOSTE, RAJ SHREE
52	Self- Closing Hinges	HETTICH, KITCH, PLUM
53	Poly Carbonate Sheet	GE LEXAN/ POLYGAL/TUFLITE
54	ACP Panel	ALUDECOR
	A constitution Was des /Fabric Densities	ALUDECOR ARMSTRONG / ANUTONE/ CREDENCE /
55	Acoustic Wooden/Fabric Paneling	TOPAKUSTIC
56	Polyvinyl Flooring	ARMSTRONG / POLY FLOR/ TARKETT
57	Glow Stud, Solar Power Stud	ROAD STAR/ 3M/ DARK EYE/ EVERY
31		DENNISON
58	Laminate Wooden Flooring	VISTA/ ACTION TESA/ ARMSTRONG/
59	Sun Control Film	PERGO 3M/ GARWARE/ SAINT GOBAIN
60	Insulation (Mineral / rock wool)	UP TIWAGA LTD / ROCKWOOL IND./ F.G.P.
	Fire Door	NAVAIR/ SHAKTI/
61		RADIANT/SIGNUM/PROMAT
62	Flush door Shutters of various thickness	MERINO/ DURO/ GREEN/ CENTURY/ KIT (SWASTIK)
63	Open cell false ceiling	ARMSTRONG /CREDENCE /HUNTER DOUGLAS
64	Calcium silicate false ceiling	AEROLITE, RAMCO, HILUX, USG BORAL
65	Gypsum Board	GYPROC BY SAINT GOBAIN, USG BORAL, ARMSTRONG
66	Fibre Cement Board	EVEREST/ USG BORAL / VISAKA
67	CPVC Pipe Fitting & Solvent	SUPREME/ ASTRAL/ ASHIRWAD / PRINCE /

		PRAKASH
68	UPVC Pipes & Fittings	SFMC / SUPREME/ FINOLEX
69	UPVC Window	FENESTA / REHAU/ ENCRAFT/ (NCL
		Wintech)/ SAINT GOBAIN
70	Friction Stay Hinges	EARL- BIHARI/ EBCO/HETTICH
71	M.S Pipes	JINDAL/ APPOLO/ SWASTIK / TATA /
		SURYA
72	Gypsum Plaster	FERROUS CRETE (FERRO-500)/ GYPROC
	CDC W-11 T'1- / L-1'	(ELITE-100)/ KERAKOL (K-100)
73	GRC Wall Tile / Jali	UNISTONE/ DALAL/ SWASTIK ALWAR / ULTRA
74	HDMR Board	CENTURY/ GREEN/ ACTION TESSA
	High Pressure Laminate(HPL)	CENTURY/ GREEN / MERINO/TRESPA/
75	riigii i ressure Lummate(III L)	FUNDERMAX
7.6	Anchor Fastener(Mechanical/ Chemical)	HILTI/ MUNGO/CANON/ FISCHER/
76	, , ,	WUERTH
77	Cupboard Lock	PLAZA/ GODREJ/ HETTICH/ HAFLEY
78	Rust remover / Rust converting primer	FOSROC/SIKA/BASF/PIDILITE
	/paint	
79	polymer based zinc rich primer	FOSROC/SIKA/BASF/PIDILITE
80	anticorrosive paint	FOSROC/SIKA/BASF/PIDILITE
81	Concrete penetrating HI-TECH Corrosion	FOSROC/SIKA/BASF/PIDILITE
	inhibitor	
82	Thixotropic Epoxy repair mortar	FOSROC/SIKA/BASF/PIDILITE
83	Latex / SBR Polymer Compound	FOSROC/SIKA/BASF/PIDILITE
84	Low viscous epoxy resin grout	FOSROC/SIKA/BASF/PIDILITE FOSROC/SIKA/BASF/PIDILITE
83	Epoxy resin for Concrete bond coat Pre-batched non-shrink polymer modified	
86	mortar	FOSKOC/SIKA/BASF/FIDILITE
	Pre-batched Pre Mixed Non- Shrink	FOSROC/SIKA/BASF/PIDILITE
87	Micro Concrete	
00	Pre-batched Pre Mixed Non- metallic	FOSROC/SIKA/BASF/PIDILITE
88	composite fiber wrapping system	
89	Epoxy for rebar/shear anchor	FOSROC/SIKA/BASF/HILTI
90	Modular kitchen basket and accessories (HETTICH/ KITCH/ PLUM / PECOCK
90	SS-304 Grade)	
91	Manhole cover /Grating	KK MANHOLE / DALAL / SWASTIK /
		HINDUSTAN
92	laminate wooden flooring	VISTA / ARMSTRONG / ACTION TESSA
93	Engineered wood Flooring	PERGO / JUNKERS / BOEN / SQUARFOOT
94	SS Pipe (304 grade) FOR WATER	JINDAL / TATA / ALFA PRESS / VIEGA
05	SUPLY Enovy flooring	FOSROC / SIKA / BASF
95	Epoxy flooring FURNITURE	FUSRUC / SINA / DASF
	T UNITI UNE	
	Work Station	GODREJ INTERIO/ HAWORTH / STEEL
96		CASE/ WIPRO/ FEATHERLITE/ HERMAN
		MLLER
	Executive Table/ other table	GODREJ INTERIO/ HAWORTH / STEEL
97		CASE/ WIPRO/ FEATHERLITE/ HERMAN
		MLLER
	Chair / Audi Chair	GODREJ INTERIO/ HAWORTH / STEEL
98		CASE/ WIPRO/ FEATHERLITE/ HERMAN
	X 1 75	MLLER
99	Lab Furniture's	KEWANEE / WALDNER / GODREJ/ WIPRO /
		FEATHERLITE

100	Hostel beds and cots	ZUARI / EVOK / GODREJ / WIPRO / FEATHERLITE
	Hospital beds	HUNTLEY / STRIKER /GODREJ /WIPRO
101	Hospital beds	/FEATHERLITE
	ITEMS FOR CLEAN ROOM / BSL /	
	SRTERLIZATION / SPECIAL LAB	
	FURNITURE	
102	Clean room Well Coiling panel coving	IClass/Nicomes/Clastro/Channel Systems
102	Clean room Wall, Ceiling panel, coving Clean room Garment cabinet, shoe rack	IClean/ Nicomac/ Clestra/ Channel Systems
	,	IClean/ Kleainzaids/ Channel Systems
104	Cleanroom Doors, Return air riser	IClean/ Nicomac/ Clestra/ Channel Systems
105	Pass box, Air Shower	IClean/ Kleainzaids / Channel Systems
106	Utility Gas piping valves and Fittings	Shavo Technologies / Excel Gas/ GDS
	(for clean room)	STARLING / Broen / Ratnamani
107	Utility Gas Pipe SS 304 Seamless (for clean room)	Excel Gas / Scoda / Venus / Dockweller
108	SS 316 L Electo polished tubing	Dockweller / Valex / Sandvik / Ratnamani
109	Chilled water pump	Grundfos/ KBL / Beacon / Wilo
110	Insulation for pipe and valves	Armaflex/ K Flex/ A flex/ Supreme
111	Auto Air vent, Y strainer	Anergy / Zoloto / Lehry
112	3 way modulating valve, Flow switch	Siemens / Honeywell
113	Humidistat, Thermostat, DP Sensor	Siemens / Honeywell
114	Magnehalic gauge	Dwyer / Sensocon / Micro precision
115	Temperature Pressure gauge	H Guru / Wika / Febig
116	Pre Insulated Ducting	RR Engineers /Asawa / Paul
117	Thermal Insulation for GI ducting	Supreme/K. Flex/A Flex/Armaflex
118	HEPA Filters, HEPA terminal, BIBO unit	AAF/Camfil/ Thermadyne / Mechmaark
119	Building Management System	Honeybell / Siemens / Johnson
120	Biometric Access System	Siemens / Vantage / ExcelLex
121	Door Interlock	Honeywell/Vantage / Drishti / Ozone
122	Thyristor Heater	KEPL/Intercool/ Rapid Cool
123	Compressed Dry Air (Oil free type)	Atlas Copco / Chicago Pneumatics Ingersol Rand / Elgi
124	Antivibration mounting	Resistoflex/ Gerb / polybond
125	Variable Frequency Drive	ABB / Danfos / Fuji
	, , , , , , , , , , , , , , , , , , ,	Kewaunee/GD-Waldner/Godrej/Citizen/ Lab
126	Lab Casework	india / lab guard
1.5-		Kewaunee/GD-Waldner/Godrej/Citizen/ Lab
127	Fume Hoods	india / lab guard
128	Utility Valves	Broen/Water Saver/FAR
129	VAV Controls	TEL TEL
130	Spot Extractor	Fumex/ Alsident
131	Exaust blower	Colasit / Plastifier/ Seat
132	Acid storage	Kewaunee/ Justrite/Asecos
133	Solvent storage (FM)	Kewaunee/ Justrite/Asecos
134	Chemical storages	Kewaunee/GD-Waldner/Godrej/Citizen
		Kewaunee/GD-Waldner/Godrej/Citizen/ Lab
135	Document Storages	india / lab guard
136	Bio safety cabinet	Kewaunee/ Klenzaids/ Esco / Fisher
137	Laminar air flow	Kewaunee/ Klenzaids/ Esco / Fisher
138	Laboratory chairs (SS)	Kewaunee/GD-Waldner/Godrej/Citizen
139	Lab Stools (SS)	Kewaunee/Godrej/Citizen/Filtotech/Universal

B:- E & M Items

S. No.	Description	Approved Makes
01	MCB(10KA)/ Isolators & MCB DB with End Box.	Legrand /Havells/ Siemens/ L&T / ABB/ Schneider/ C&S.
02	MCCB	Legrand /Havells/ Siemens/ L&T / ABB/ Schneider/ C&S.
03	MCCB BOX	Legrand /Havells/ Siemens/ L&T / ABB/ Schneider/ C&S.
04	Modular type switch/ socket, TV socket, Fan Regulator.	Havells Crabtree / L&T/ ABB/ Wipro North West/ Legrand(Arteor/ Myrius)/ Schneider (Zencelo).
05	Steel conduit pipe and Accessories (ISI)	BEC/ AKG/ NIC / Steel Krafts
04	PVC conduit pipe and Accessories(ISI)	BEC/ AKG/ NIC
05	Junction Boxes/ MS Boxes	Havells Crabtree / Anchor / North West / Legrand
06	Bushes	PVC/ Nylon
07	FRLS PVC insulated copper conductor cable	Polycab / Finolex / Havells/ KEI/ Universal
08	LED Light Fixture	Philips/ Trilux/ Bajaj/ Wipro/Crompton/ Havells.
09	Ceiling Fans (BLDC) & Wall Fan	Havells/ Atomberg/ Bajaj/ Crompton/USHA.
10	Exhaust Fan/ Fresh Air Fan	Havells/ Bajaj/ Crompton/USHA.
11	Industrial type socket	Legrand /Havells/ Siemens/ L&T / ABB/ Schneider/ C&S.
12	DLP U-PVC channel & accessories	Schneider / Legrand
13	Modular Plate & Cover Plate	Havells Crabtree / L&T/ ABB/ Wipro North West/
		Legrand(Arteor/ Myrius)/ Schneider (Zencelo).
14	Distribution Board	Legrand /Havells/ Siemens/ L&T / ABB/ Schneider/ C&S.
15	XLPE Alumium/ Copper conductor Armoured cable	Havells/ Gloster/ Polycab/ Finolex/ RR kabel/ KEI/ Universal/ Rallison
16	Multifunction Meter	L&T/ AE/ Schneider/ Rishabh/ HPL
17	Ammeter	L&T/ AE/ Universal/ Rishabh/ Meco/ Kaycee/ Enercom
18	Voltmeter	L&T/ AE/ Universal/ Rishabh/ Meco/ Kaycee/ Enercom
19	Frequency Meter	Digitron/ AE/ Rishabh/ Meco/ Keltron.
20	CT's	L&T/AE/ KAPPA/ Pragati/ Marshal/ L&T
21	Selector Switches	L&T/AE/ KAPPA/ Pragati/ Marshal/ L&T
22	Contractors	L&T/ Seimens/ GE power/ Crompton/ Havells/ Legrand
23	Push button & Pilor lamps	BCH/ L&T/ Seimens/ Vaishno
24	LED indicating Lights	L&T/ Siemens/ Kaycee/ Crompton/ Vaishno
25	GI Pipe	Jindal Steel/ Jindal Hisar/ Sail/ Tata
26	DW HDPE Pipe	Reliance/ Duraline/ Hasti
27	Cat 6 LAN Cable	Legrand/ Molex/ Amp
28	Air conditioners	Mitsubishi/ O general/ Hitachi/ Daikin/ Blue Star/ Carrier/ LG/ Lloyds/ Panasonic/ Voltas
29	Access Control System	Bosch/ Honeywell/ HID/ Nextwatch
30	Intruder Alarm Systerm	Ademco/ bosch/ DSC/ Honeywell
31	Cable raceway floor/ wall mounted & Accessories(MS/G.I)	Legrand/ AKG/ BEC/ ESSAR/ Honeywell/ Godrej.
32	Sandwitch Bus trunking/ Rising Main	C&S/ L&T/ Schneider/ ABB.
33	Telephone wire	Delton/ Finolex/ Havells/ Skytone
34	Occupancy Sensor	Wipro/ Schneider/ Honeywell/ Seimens/ Bosch
35	Gooseneck Microphone	Televic/ Beyerdynamic/ Bosch/ Bose/ Sennheiser
36	Amplifier	Crown/ Extrom/ Crestron
37	24 Port Switch	Cisco/ Netgear/ Hp/ Juniper
38	8 Port LIU	Legrand/ AMP/ Molex
39	16 Port Gigabit POE Switch	Netgear/ Juniper/ Cisco
40	HDMI/ USB Cable	AMX/ Crestron/ Manhatten
41	AV Speaker	JBL/ Bosch/ Bose/ Sony
42	CCTV Camera	Pelco/ Bosch/ Honeywell
43	DVR (Digital Video Recorder)	Bosch/ Honeywell/ Pelco
44	Fire Suppression System	Minimax/ Ceasefire/ Ansul
45	Fire Panel	Notifier/ Johnson Control/ Fike/ Cooper/ Bosch/ Honeywell
46	PA System	Notifier/ Johnson Control/ Fike/ Cooper/ Bosch/ Honeywell

47	Addressable Heat/ Smoke detector/ Hooter/ RI/	Notifier/ Johnson Control/ Fike/ Cooper/ Bosch/
	Pullstation/	Honeywell
48	Conventional Heat/ Smoke detector/ Hooter/ RI/	System Sensor/ Cooper/ GST/ Ravel/ Fike/ Essar/
	Pullstation/	Honeywell/ Bosch/ Bosch
49	Cable joint Kit	Raychem/ M-Seal/ Densons/ 3M

BID SUBMISSION

ONLINE BID SUBMISSION

The Online bids (complete in all respect) must be uploaded online in two Envelops as explained below: -

Sl. No.	Documents	Content	File
1.	Technical Bid	Demand Draft/Pay order or Banker`s Cheque /Deposit at Call Receipt/FDR of any Scheduled Bank against EMD.	Types .PDF
2.		Enlistment order of contractor.	.PDF
3.		Certificate of work experience.	.PDF
4.		Certificate of Registration of GST and acknowledgment of up to date field return of GST.	.PDF
5.		Affidavit as per Notice Inviting Tender Condition 1.2.2 page 20 of NIT. (Affidavit shall be purchased/ notarized between date of publishing and last date of submission of bids beside this NIT/Tender ID and name of work must be mentioned on the affidavit.).	.PDF
6. 7.		Acceptance to execute INTEGRITY PACT. Undertaking as per on firm's letter head.	.PDF .PDF
		"The physical EMD shall be deposited by me / us with the Authority inviting the tender, in case I / we become the lowest tenderer, within a week of the opening of financial bid, otherwise, department may reject the tender and also take action to debar me / us from tendering in any form in IIT Delhi"	
8.		ESI and EPF Registration.	PDF
9. 10		FORM "F" (Duly filled with all required details In case of Partnership firm if all the papers of tender not signed by all the partners than a power of attorney authorizing the person who has signed the tender paper must be uploaded with the tender documents.	.PDF PDF
11		Annexure-I (duly filled & signed by the bidders)	PDF
12	1	Annexure-II (duly filled & signed by the bidders)	PDF
13		Annexure-III (duly filled & signed by the bidders)	PDF
14		Any other documents specified in NIT	PDF
nvelope	<u>-2</u>		
Sl. No.	TYPES	Content	
1.	Financial Bid	Price bid should be submitted in BOQ format.	.Xls

All above documents shall be as per Tender Notice.

PART 'C'

SCHEDULE OF QUANTITY

Name of work:- Comprehensive Maintenance of Civil work, Horticulture, Public Health Work, Service of Housekeeping and Round the clock O & M services for public health work at Sonipat Campus of IIT Delhi for the year 2025-2026.

S.No	Description	Unit	Qty.	Rate Rs. (Inclusive of GST)	Amount Rs.
	Civil Work			Í	
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge:				
1.1	All kinds of soil	Sqm	200		
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
2.1	All kinds of soil.	Cum	20		
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	30		
4	Extra for levelling & neatly dressing of disposed soil completely as directed by Engineer-in-charge.	Cum	100		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:				
5.1	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	Cum	15		
6	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	Sqm	50		

	Reinforced cement concrete work in walls (any			
	thickness), including attached pilasters, buttresses,			
7	plinth and string courses, fillets, columns, pillars,			
,	piers, abutments, posts and struts etc. above plinth			
	level up to floor five level, excluding cost of			
	centering, shuttering, finishing and reinforcement:			
	1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived			
7.1	from natural sources: 3 graded stone aggregate 20	Cum	15	
,,,,	mm nominal size derived from natural sources)	Cum	10	
	Reinforced cement concrete work in beams,			
	suspended floors, roofs having slope up to 15°			
	landings, balconies, shelves, chajjas, lintels, bands,			
	plain window sills, staircases and spiral stair cases			
8	above plinth level up to floor five level, excluding	Cum	10	
	the cost of centering, shuttering, finishing and			
	reinforcement with 1:1.5:3 (1 cement : 1.5 coarse			
	sand(zone-III) derived from natural sources : 3			
	graded stone aggregate 20 mm nominal size derived			
	from natural sources).			
9	Centering and shuttering including strutting,			
9	propping etc. and removal of form for			
0.1	Walls (any thickness) including attached pilasters,	G	100	
9.1	butteresses, plinth and string courses etc.	Sqm	100	
9.2	Shelves (Cast in situ)	Sqm	50	
9.3	Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	50	
7.5	Steel reinforcement for R.C.C. work including	Sqiii	30	
10				
10	straightening, cutting, bending, placing in position			
	and binding all complete above plinth level.			
10.1	Thermo-Mechanically Treated bars of grade Fe-	Kg.	1500	
10.1	500D or more.	8.		
	Brick work with common burnt clay F.P.S.			
11	(non modular) bricks of class designation 7.5 in			
	foundation and plinth in:			
11.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	10	
11.1		Cum	10	
	Brick work with common burnt clay F.P.S.			
12	(non modular) bricks of class designation 7.5 in			
1-	superstructure above plinth level up to floor V			
	level in all shapes and sizes in :			
12.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	5	
	Half brick masonry with common burnt clay			
13	` '			
	designation 7.5 in superstructure above plinth			
	level up to floor V level.			
13.1	Cement mortar 1:4 (1 cement :4 coarse sand)	Sqm	50	
	Extra for providing and placing in position 2	-		
14	Nos 6mm dia. M.S. bars at every third course	Sqm	50	
1-7	of half brick masonry.	Sqiii	50	
	· · · · · · · · · · · · · · · · · · ·			
	Providing and fixing 18 mm thick gang saw			
	cut, mirror polished,			
	premoulded and prepolished, machine cut for			
	kitchen platforms, vanity counters, window			
	sills, facias and similar locations of required			
	_			
15	size, approved shade, colour and texture laid			
	over 20 mm thick base cement mortar 1:4 (1			
	cement: 4 coarse sand), joints treated with			
	white cement, mixed with matching pigment,			
	epoxy touch ups, including rubbing, curing,			
	moulding and polishing of edges to give high			
	gloss finish etc. complete at all levels.			
1	gross minsir etc. complete at an ieveis.			_1

	D.: M Dl.:			<u> </u>	
15.1	Raj Nagar Plain white marble/ Udaipur green				
	marble/ Zebra black marble	Carr	20		
15.1.1	Area of slab upto 0.50 sqm Granite stone slab of colour black,	Sqm	20		
15.2	,				
15 0 1	Cherry/Ruby red	C	10		
15.2.1	Area of slab upto 0.50 sqm	Sqm	10		
	Providing edge moulding to 18 mm thick				
1.0	marble stone counters, Vanities etc., including				
16	machine polishing to edge to give high gloss				
	finish etc. complete as per design approved by				
1.6.1	Engineer-in-Charge.	3.5	40		
16.1	Marble work	Metre	40		
16.2	Granite work	Metre	20		
	Extra for fixing marble /granite stone, over and				
	above corresponding basic item, in facia and				
17	drops of width upto 150 mm with epoxy resin	Metre	15		
	based adhesive, including cleaning etc.				
	complete.				
	Mirror polishing on marble work/Granite				
18	work/stone work where ever required to give	Sqm	30		
	high gloss finish complete.				
	Providing and fixing Ist quality ceramic glazed				
	wall tiles conforming to IS: 15622 (thickness to				
	be specified by the manufacturer), of approved				
	make, in all colours, shades except burgundy,				
	bottle green, black of any size as approved by				
19	Engineer-in-Charge, in skirting, risers of steps	Sqm	80		
17	and dados, over 12 mm thick bed of cement	Sqiii	00		
	mortar 1:3 (1 cement : 3 coarse sand) and				
	jointing with grey cement slurry @ 3.3kg per				
	sqm, including pointing in white cement mixed				
	with pigment of matching shade complete.				
	D '1' 1 C' 1 TOY 1 1 C' 1 1				
	Providing and fixing ISI marked flush door				
	shutters conforming to IS: 2202 (Part I) non-				
	decorative type, core of block board				
20	construction with frame of 1st class hard wood				
	and well matched commercial 3 ply veneering				
	with vertical grains or cross bands and face				
	veneers on both faces of shutters:				
	35 mm thick including ISI marked Stainless				
20.1	Steel butt hinges with necessary screws	Sqm	10		
	Providing and fixing aluminium extruded				
	section body tubular type universal hydraulic				
	door closer (having brand logo with ISi, IS:				
	3564, embossed on the body, door weight upto				
21	36 kg to 80 kg and door width from 701 mm to	Each	30		
	1000 mm), with double speed adjustment with				
	necessary accessories and screws etc.				
	complete.				
	Providing and fixing chromium plated brass				
	100 mm mortice latch and lock with 6 levers				
22	and a pair of lever handles of approved quality	Each	30		
	with necessary screws etc. complete.	<u> </u>	l	<u> </u>	

	Drawiding and fiving appaid quality abnomium			
	Providing and fixing special quality chromium			
23	plated brass cupboard locks with six levers of			
	approved quality including necessary screws			
22.1	etc. complete.	T 1	50	
23.1	Size 50 mm	Each	50	
	Providing and fixing aluminum hanging floor			
	door stopper, ISI marked, anodised (anodic			
24	coating not less than grade AC 10 as per IS:			
27	1868) transparent or dyed to required colour			
	and shade, with necessary screws etc.			
	complete.			
24.1	Twin rubber stopper	Each	100	
	Providing & Fixing decorative high pressure			
	laminated sheet of plain /wood grain in gloss /			
	matt/ suede finish with high density protective			
25	surface layer and reverse side of adhesive			
	bonding quality conforming to IS: 2046 Type			
	S, including cost of adhesive of approved			
	quality.			
25.1	1.0 mm thick	Sqm	60	
20.1	Providing and fixing stainless steel (SS-304	Sqiii	00	
	grade) friction hinges to the side/top hung			
26	uPVC windows, of approved quality, with			
20	necessary stainless steel screws etc. as per			
	direction of Engineer-in-charge.			
26.1	250 x 19 x 1.9 mm	Each	40	
26.2	300 x 19 x 1.9 mm	Each	60	
26.3	350 x 19 x 1.9 mm	Each	60	
26.4	400 x 19 x 1.9 mm	Each	60	
	Providing and fixing cupboard shutter with			
	19mm thick one side decorative and other side			
	balancing lamination factory pressed BWP			
	grade marine ply as per IS 710 of approved			
	brand including 2mm thick PVC edge banding			
27	tape with hot glue by edge bending machine	Sqm	40	
	etc. with auto closing spring loaded hinges			
	(hydraulic type) etc. complete as per direction			
	of Engineerin- charge.(Payment of providing			
	and fixing auto closing hinges shall be paid			
	separately)			
	Providing and fixing 19mm thick both side			
	balancing lamination factory pressed BWP			
	grade marine ply as per IS 710 of approved			
28	brand boxes, shelves, racks, almirah, cupboard	Sqm	70	
20	and drawer etc. including necessary nails,	bqm	70	
	screws etc. complete as per direction of			
	Engineer-in-charge.			
	Providing and fixing stainless steel fancy			
	handle of approved make fixed with SS screws			
29	etc. complete as per direction of Engineer-in-			
20.1	charge.	Eagle	20	
29.1	200 mm	Each	20	
	Description and Control 4.1.1. 4.1.0.1.1			
	Providing and fixing stainless steel soft closing			
30	spring hinges at 0 degree hinges (hydraulic	Each	40	
30		Each	40	

	in also disconnections are account as a social be and and			
	including making necessary recess in board and			
	finished etc. complete as per direction of			
	Engineer-in-charge.			
	Providing and fixing stainless steel soft closing			
	heavy type telescopic drawer channels of	One		
31	approved make 500 mm long with screws etc.		40	
	complete as per directions of Engineer- in-	Set		
	charge.			
	Providing and fixing 2mm thick 16 to 19mm			
	wide PVC edge binding tape of approved			
	quality for cupboard/wardrobe shutters			
32	including necessary synthetic resin hot pressed	Metre	100	
	to edges on binding machine etc. complete as			
	per directions of Engineer- in-charge.			
	Steel work in built up tubular (round, square or			
	rectangular hollow tubes etc.) trusses etc.,			
33	including cutting, hoisting, fixing in position			
	and applying a priming coat of approved steel			
	primer, including welding and bolted with			
	special shaped washers etc. complete.			
33.1	Hot finished welded type tubes	Kg.	1000	
	Steel work welded in built up sections/ framed			
	work, including cutting, hoisting, fixing in			
34	position and applying a priming coat of			
	approved steel primer using structural steel etc.			
	as required.			
34.1	In gratings, frames, guard bar, ladder, railings,	V.	600	
34.1	brackets, gates and similar works	Kg.	000	
	Kota stone slab flooring over 20 mm (average)			
	thick base laid over and jointed with grey			
25	cement slurry mixed with pigment to match the			
35	shade of the slab, including rubbing and			
	polishing complete with base of cement mortar			
	1:4(1 cement: 4 coarse sand):			
35.1	25 mm thick	Sqm	40	
	Providing and laying rectified Glazed Ceramic floor	•		
	tiles of size 300x300 mm or more (thickness to be			
	specified by the manufacturer), of 1st quality			
	conforming to IS: 15622, of approved make, in all			
36	colours, shades, except White, Ivory, Grey, Fume	Sqm	40	
30	Red Brown, laid on 20 mm thick Cement Mortar 1:4	Sqiii	70	
	(1 Cement : 4 Coarse sand), jointing with grey			
	cement slurry @ 3.3 kg/ sqm including pointing the			
	joints with white cement and matching pigments			
	etc., complete.			+
	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS:			
37	13592 Type A, including jointing with seal			
]	ring conforming to IS: 5382, leaving 10 mm gap for			
	thermal expansion, (i) Single socketed pipes.			
37.1	75 mm diameter	Metre	40	
37.2	110 mm diameter	Metre	50	
	Providing and fixing on wall face unplasticised -			
	PVC moulded fittings/ accessories for unplasticised			
38	Rigid PVC rain water pipes conforming to IS:			
	13592 Type A, including jointing with seal ring			
	conforming to IS: 5382, leaving 10 mm gap for			
38.1	thermal expansion. 75 mm bend	East-	10	
36.1	13 mm uchu	Each	10	

38.2	110 mm bend	Each	10	
	Providing and fixing precoated galvanised iron			
	profile sheets (size, shape and pitch of corrugation			
	as approved by Engineer-in-charge) 0.50 mm (+			
	0.05 %) total coated thickness with zinc coating 120			
	grams per sqm as per IS: 277, in 240 mpa steel			
	grade, 5-7 microns epoxy primer on both side of the			
	sheet and polyester top coat 15-18 microns. Sheet			
	should have protective guard film of 25 microns			
39	minimum to avoid scratches during transportation	Sqm	50	
	and should be supplied in single length upto 12	Sqiii	30	
	metre or as desired by Engineer-in- charge. The			
	sheet shall be fixed using self drilling /self tapping			
	screws of size (5.5x 55 mm) with EPDM seal,			
	complete upto any pitch in horizontal/ vertical or			
	curved surfaces, excluding the cost of purlins,			
	rafters and trusses and including cutting to size and			
	shape wherever required.			
	Providing and fixing precoated galvanised steel			
	sheet roofing accessories 0.50 mm (+0.05 %) total			
	coated thickness, Zinc coating 120 grams per sqm			
40	as per IS: 277, in 240 mpa steel grade, 5-7 microns			
40	epoxy primer on both side of the sheet and polyester			
	top coat 15-18 microns using self drilling/ self			
	tapping screws complete:			
40.1	Gutter (600 mm over all grith)	Metre	20	
41	12 mm cement plaster:	Wietre	20	
41.1	1:4 (1 cement : 4 fine sand)	Sqm	100	
42	15 mm cement plaster:	Sqiii	100	
42.1	1:4 (1 cement : 4 fine sand)	Sqm	100	
12.1	Providing and applying plaster of paris putty of 2	bqiii	100	
43	mm thickness over plastered surface to prepare the	Sqm	500	
13	surface even and smooth complete.	bqiii	300	
	Painting with synthetic enamel paint of approved			
44	brand and manufacture to give an even shade:			
44.1	Two or more coats on new work	Sqm	200	
11.1	Providing and applying white cement based	bqiii	200	
	putty of average thickness 1 mm, of approved			
1.5	1 2 2	C	200	
45	brand and manufacturer, over the plastered wall	Sqm	300	
	surface to prepare the surface even and smooth			
	complete.			
	Wall painting with premium acrylic emulsion paint			
	of interior grade, having VOC (Volatile Organic			
46	Compound) content less than 50 grams/ litre of			
	approved brand and manufacture, including			
	applying additional coats wherever required to			
	achieve even shade and colour.	~	4000-	
46.1	One or more coats on old work	Sqm	12000	
	Removing dry or oil bound distemper, water			
4.7	proofing cement paint and the like by scrapping,	C	700	
47	sand papering and preparing the surface smooth	Sqm	500	
	including necessary repairs to scratches etc.			
	complete			
40	Painting with synthetic enamel paint of approved			
48	brand and manufacture of required colour to give an			
40.4	even shade :	a	4500	
48.1	One or more coats on old work	Sqm	4500	
49	French spirit polishing:	Sqm	500	
49.1	One or more coats on old work		. LIVI	

			ı	I
50	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade			
50.1	Old work (one or more coats applied @ 0.83 ltr/10 sqm).	Sqm	1000	
51	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.			
51.1	With cement mortar 1:4 (1 cement : 4 fine sand)	Sqm	150	
52	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty:	•		
52.1	Float glass panes of nominal thickness 5 mm (weight not less than 12.5kg/sqm)	Sqm	20	
53	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineerin- charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding. Note: - This item to be used for maintenance work judicially, necessary deduction for scaffolding in the existing item to be done.	Sqm	500	
54	Cleaning of terrace/loft water storage tank (inside surface area) upto 2000 litre capacity at all heights with coconut brushes, duster etc., removal of silt, rubbish from the tank and cleaning the tank with fresh water disinfecting with bleaching powder @ 0.5gm per litre capacity of tank including marking the date of cleaning on the side of tank body with the help of stencil and paint and disposing of malba all complete as per direction of Engineer-in-Charge. (The old date already written on tank should be removed with paint remover or black paint and if date is not written with the stencil or old date is not removed deduction will be made @ Rs. 0.10 per litre) (if during cleaning any GI fittings or ball cock is damaged that is to be repaired by contractor at his own cost and nothing extra will be paid on this account)	Litre	50000	
55	Cleaning and desilting of gully trap chamber, including removal of rubbish mixed with earth etc. and disposal of same, all as per the direction of Engineer-in-charge.	Each	50	
56	Cleaning of under ground sump, Over Head R.C.C. Tank (independent staging) including disposal of	Sqm	100	

Charge. The cleaning shall consist following operations: (i) Tank shall be emptied of water by pumping & bottom shall be cleaned of silt and other deposits. (ii) Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Fingineer-in-charge. 57.1 design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material ameans including stacking of serviceable material means including stacking of serviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismatled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 minital lead, for all leads including all liths involved. 60.1 Supplying at site: Welded steel wire labric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete li-24 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in panches as required including consolidation finishing and tamping complete. Providing and laying 50 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size in panches as per direction, of approved size, design & shape in the pr				1	1	т
Charge. The cleaning shall consist following operations: (i) Tank shall be emptied of water by pumping & bottom shall be cleaned of silt and other deposits. (ii) Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-Charge. 57.1 Nominal concrete 13:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material amans including stacking of serviceable material means including stacking of serviceable material means including stacking of serviceable material means including stacking of serviceable material unserviceable, dismantled or waste materials by mechanical means, including publish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, undough to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 minital lead, for all leads including all lifts involved. 60.1 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating smooth etc, complete as per direction of Engineer in-c		slit and rubbish, all as per direction of Engineer-in-				
operations:- (i) Tank shall be capacid of water by pumping & bottom shall be cleaned of sitl and other deposits. (ii) Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water. (iii) Cholimation of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-Charge. 757. In some surface shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge. Nominal concrete 1:3:6 or richer mix (i/e equivalent disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 858. In cement mortar Demolishing brick work manually/ by mechanical mans including stacking of serviceable material within 50 metres lead as per direction of Engineer-in-charge. 858. In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 mindle edd, for all leads including all lifts involved. 860. Supplying at site: 870. Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of primer (Priming & Painting to be paid for separately). 871. Cement concrete 1:2:4 (1 cement; 2 coanse sand; 4 graded stone aggregate 40 mm nominal size) in pawemens, laid to required stope and camber in pamels as required including consolidation finishing and tamping complete. 872. Providing and laying of mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size in pawemens, laid to required s		Charge. The cleaning shall consist following				
(i) Tank shall be cleaned of sitt and other deposits. (ii) Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 merts ead as per direction of Engineer-in - charge. 57.1 Nominal concrete 1:3:6 or richer mix (i/e equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material and manual disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. S8.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size in pavements, laid to required slope and camber in pavements, la						
bottom shall be cleaned of silt and other deposits. (ii) Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. 57.1 design mix) Demolishing brick work manually by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (I cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pawements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidation gand grouting with jamuna sand, including finishing and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60 mm thick factory made cement concrete interlocking pawer block of M -30 grade made by block making ma		-				
(ii) Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge. Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. 57.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and siposal of unserviceable material and sposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 5 m minital lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and tamping complete. Providing and laying 60mm thick factory made cement concrete incrlocking paver block of M30 grade made by block making machine with strong vibratory compaction, of approved size, design						
scrubbed thoroughly with wire brush etc. and pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. S8.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pawements, laid to required slope and camber in panels as required including consolidation finishing and tumping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size in pawed as a required including consolidation finishing and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking pawer block of M -30 grade made by block making machine with strong and grouting with jamuna sand, including 50mm thick compacted bed of coarse sand, fill						
pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead us per direction of Engineer-in-charge. 57.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong grade made by block making machine with strong and including 50mm thick compacted bed of coarse sand, filling the joints with		(ii) Entire surface area of the sump shall then				
pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead us per direction of Engineer-in-charge. 57.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong grade made by block making machine with strong and including 50mm thick compacted bed of coarse sand, filling the joints with						
(iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be trenoval from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and siposal of unserviceable material shad disposal of unserviceable material shad means including to inserviceable material unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. Supplying at site: Wedded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (I cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pamels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size in pamels as required including consolidation finishing and grouting with jamunas and, including finishing sand grouting with jamunas and, including finishing and grouting with jamunas and, including finishing sand grouting with jamunas and, including finishing sand divided cement concrete interlocking paver block of M -30 grade made by block making machine with strong grade made by block making machine with strong and complete as per direction of Engineer in-charge. Providing and laying 40 near ground level factory						
chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. 57.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size in panels as required including consolidating finishing and grouting with jamuna sand, including fini						
(iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. 57.1 design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond \$50 minitial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size in panels as required including consolidating and grouting with jamuna sand, including finishing and grouting						
jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. 57.1 Domolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unleading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial leads, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of chamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (I cement: 2 coarse sand; 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm mominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong with particles of the providing sould required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level foctory		chlorine.				
jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. 57.1 Domolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unleading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial leads, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of chamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (I cement: 2 coarse sand; 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm mominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong with particles of the providing sould required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level foctory		(iv) The treated surface shall be dried using air				
the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer in - charge. 57.1 design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 59 Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in panels as required including consolidating and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing and tamping complete. Providing and laying 60mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing sand type of the providing						
(v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. 57.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, undeading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of camel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong short experience in charge. Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong short experience in charge. Providing and laying 61 magnerer in-charge. Providing and laying at or near ground level factory						
ultraviolet radiation etc. as per direction of Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. 57.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying 61 or near ground level factory						
Engineer-in-Charge Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. 57.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer in - charge. 57.1 Mominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, expond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wise fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
mechanical means including disposal of material within 50 metres lead as per direction of Engineer in charge. 57.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of chamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 75 mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory		Engineer-in-Charge				
mechanical means including disposal of material within 50 metres lead as per direction of Engineer in charge. 57.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of chamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 75 mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory		Demolishing cement concrete manually/ by				
within 50 metres lead as per direction of Engineer in - charge. 57.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size in cluding spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	57					
Sominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.						
Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. Cum 2		in - charge.				
Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. Cum 2	·	Nominal concrete 1:3:6 or richer mix (i/c equivalent				
Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M · 30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	57.1		Cum	2		
means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all litts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying 30 mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory		<u> </u>		+		+
and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & supp. laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
metres lead as per direction of Engineer-in-charge. 58.1 In cement mortar Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	58					
Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	30	and disposal of unserviceable material within 50				
Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory		metres lead as per direction of Engineer-in-charge.				
Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	58.1		Cum	2		
unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	30.1		Cum			-
mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	50	mechanical means, including loading, transporting,	C	200		
or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. 60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	39		Cum	200		
initial lead, for all leads including all lifts involved. Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
60 Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	60					
rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory		Welded steel wire fabric of required width having				
60.1 enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
primer (Priming & Painting to be paid for separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	60.1		V a	100		
Separately). Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	00.1		Kg.	100		
Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory		Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4				
61 pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
panels as required including consolidation finishing and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	61		Cum	10		
and tamping complete. Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	01		Cuiii	10		
Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory		1				
Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory		and tamping complete.		<u> </u>	<u> </u>	
dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory				1		
including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge. Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
and grouting with Jamuna sand, including finishing smooth etc. complete as per direction of Engineer in-charge Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	62		Sqm	40		
in-charge Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory			1			
Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory		smooth etc. complete as per direction of Engineer				
Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory		in-charge.				
cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory				1		
including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	63		Sam	200		
including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory	0.5	shape, laid in required colour and pattern over and	Sqiii	200		
sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory						
Providing and laying at or near ground level factory		sand filling the joints with line sand etc. all		1		
1 1 1 1 4 634.07 1		complete as per the direction of Engineer-in-charge.				
made kerb stone of M-25 grade cement concrete in C 1		complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory				
	64	complete as per the direction of Engineer-in-charge.	Const	1		
jointed with cement mortar 1:3 (1 cement: 3 coarse	64	complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in	Cum	1		
Joined with cement mortal 1.5 (1 cement, 5 coarse	64	complete as per the direction of Engineer-in-charge. Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature,	Cum	1		

_			ı	T	
	sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge). Providing and fixing G.I. chain link fabric				
65	fencing of required width in mesh size 25x25 mm made of G.I. wire of dia 3 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge.	Sqm	40		
66	Providing and laying C.C. pavement of mix M-25 with ready mixed concrete from batching plant. The ready mixed concrete shall be laid and finished with screed board vibrator, vacuum dewatering process and finally finished by floating, brooming with wire brush etc. complete as per specifications and directions of Engineer-incharge. (The panel shuttering work shall be paid for separately). (Note:- Cement content considered in this item is @ 330 kg/cum. Excess/less cement used as per design mix is payable/ recoverable separately).	Cum	7		
67	Taking out existing kerb stones of all types from footpath/central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	Metre	50		
68	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	Sqm	250		
69	Laying old cement cocrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	Sqm	250		
70	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to Eureopean type W.C. of quality and make as approved by Engineer - in - charge.	Each	20		

	Draviding and fiving CD Dragg 22mm size				
71	Providing and fixing CP Brass 32mm size	г 1	50		
71	Bottle Trap of approved quality & make and as	Each	50		
	per the direction of Engineer-in-charge.				
	Providing and fixing P.V.C. waste pipe for sink				
72	or wash basin including P.V.C. waste fittings				
	complete.				
72.1	Flexible pipe				
72.1.1	32 mm dia	Each	50		
, 2,1,1,1	Providing and fixing 600x450 mm beveled				
	edge mirror of superior glass (of approved				
73	quality) complete with 6 mm thick hard board	Each	20		
7.5	ground fixed to wooden cleats with C.P. brass	Lacii	20		
	-				
	screws and washers complete.				
	Providing and fixing 600x120x5 mm glass				
	shelf with edges round off, supported on				
74	anodised aluminium angle frame with C.P.	Each	20		
, -	brass brackets and guard rail complete fixed				
	with 40 mm long screws, rawl plugs etc.,				
	complete.				
74.1	Providing and fixing toilet paper holder:				
74.1.1	C.P. brass	Each	20		
	Providing and fixing white vitreous china				
	battery based infrared sensor operated urinal of				
	approx. size 610 x 390 x 370 mm having pre &				
	post flushing with water (250 ml & 500 ml		_		
75	consumption), having water inlet from back	Each	5		
	side, including fixing to wall with suitable				
	brackets all as per manufacturers specification				
	and direction of Engineer-in-charge.				
	Providing and fixing Chlorinated Polyvinyl				
	Chloride (CPVC) pipes, having thermal				
	stability for hot & cold water supply, including				
	•				
76	all CPVC plain & brass threaded fittings,				
76	including fixing the pipe with clamps at 1.00 m				
	spacing. This includes jointing of pipes &				
	fittings with one step CPVC solvent cement				
	and testing of joints complete as per direction				
	of Engineer in Charge				
76.1	15 mm nominal dia Pipes	Metre	50		
76.2	20 mm nominal dia Pipes	Metre	50		
76.3	25 mm nominal dia Pipes	Metre	50		
	Providing and fixing G.I. pipes complete with				
77	G.I. fittings and clamps, i/c cutting and making				
	good the walls etc.				
77.1	15 mm dia nominal bore	Metre	50		
77.2	20 mm dia nominal bore	Metre	50		
77.3	25 mm dia nominal bore	Metre	50		
78	Providing and fixing gun metal gate valve with C.I.				
	wheel of approved quality (screwed end):				
78.1	20 mm nominal bore	Each	10		
78.2	25 mm nominal bore	Each	5		
78.3	50 mm nominal bore	Each	5		
79	Providing and fixing ball valve (brass) of				
	approved quality, High or low pressure, with				
	plastic floats complete :				
79.1	15 mm nominal bore	Each	20		
79.2	20 mm nominal bore	Each	20		
				1	1

80	Providing and fixing gun metal non- return			
00	valve of approved quality (screwed end):			
80.1	25 mm nominal bore			
80.1.1	Horizontal	Each	10	
		Eacii	10	
81	Providing and fixing uplasticised PVC			
01.1	connection pipe with brass unions:			
81.1	45 cm length			
81.1.1	15 mm nominal bore	Each	200	
82	Providing and fixing C.P. brass shower rose			
	with 15 or 20 mm inlet:			
82.1	100 mm diameter	Each	15	
83	Repainting G.I. pipes and fittings with			
	synthetic enamel white paint with one coat of			
	approved quality:			
83.1	20 mm diameter pipe	Metre	200	
83.2	25 mm diameter pipe	Metre	200	
83.3	40 mm diameter pipe	Metre	200	
83.4	50 mm diameter pipe	Metre	200	
84	Providing and fixing G.I. Union in existing			
	G.I. pipe line, cutting and threading the pipe			
	and making long screws, including			
	excavation, refilling the earth or cutting of			
	wall and making good the same complete			
	wherever required :			
84.1	15 mm nominal bore	Each	20	
84.2	20 mm nominal bore	Each	20	
84.3	25 mm nominal bore	Each	10	
84.4	50 mm nominal bore	Each	10	
85	Providing and fixing C.P. brass bib cock of	Buen	10	
0.5	approved quality conforming to IS:8931:			
85.1	15 mm nominal bore	Each	10	
86	Providing and fixing C.P. brass long body bib	Lacii	10	
80	cock of approved quality conforming to IS			
	standards and weighing not less than 690 gms.			
86.1	15 mm nominal bore	Each	10	
87		Eacii	10	
87	Providing and fixing C.P. brass stop cock			
	(concealed) of standard design and of approved			
07.1	make conforming to IS:8931.	T1-		
87.1	15 mm nominal bore	Each	6	
88	Providing and fixing C.P. brass angle valve for			
	basin mixer and geyser points of approved			
00.1	quality conforming to IS:8931	T71	40	
88.1	15mm nominal bore	Each	40	
89	Providing and fixing C.P. Brass extension	Each	200	
	nipple (size 15mmx50mm) of approved make			
	and quality as per direction of Engineer-in-			
00	charge.			
90	Providing & fixing chrome plated brass battery			
	based infrared sensor operated pillar cock,			
00.1	having foam flow technology.	-	4.0	
90.1	15 mm nominal bore	Each	10	
91	Providing and laying non-pressure NP2 class			
	(light duty) R.C.C. pipes with collars jointed			
	with stiff mixture of cement mortar in the			
	proportion of 1:2 (1 cement : 2 fine sand)			
	including testing of joints etc. complete:			
	more and to string or joints over compress.	l l		

91.1	150 mm dia. R.C.C. pipe	Metre	50	
92	Supplying and fixing C.I. cover 300x300 mm	Each	50	
1 12	without frame for gully trap (standard pattern)	Lacii	30	
	the weight of cover to be not less than 4.5 kg			
93	Providing and fixing aluminium work for			
93	doors, windows, ventilators and partitions with			
	extruded built up standard tubular sections/			
	appropriate Z sections and other sections of			
	approved make conforming to IS: 733 and IS:			
	1285, fixing with dash fasteners of required dia			
	and size, including necessary filling up the gaps			
	at junctions, i.e. at top, bottom and sides with			
	required EPDM rubber/ neoprene gasket etc.			
	Aluminium sections shall be smooth, rust			
	free, straight, mitred and jointed mechanically			
	wherever required including cleat angle,			
	Aluminium snap beading for glazing /			
	paneling, C.P. brass / stainless steel screws, all			
	complete as per architectural drawings and the			
	directions of Engineer-in-charge. (Glazing,			
	paneling and dash fasteners to be paid for			
02.1	separately):			
93.1	For fixed portion	V~	250	
93.1.1	Powder coated aluminium (minimum thickness	Kg.	250	
0.4	of powder coating 50 micron)			
94	For shutters of doors, windows & ventilators			
	including providing and fixing hinges/ pivots			
	and making provision for fixing of fittings			
	wherever required including the cost of EPDM			
	rubber / neoprene gasket required (Fittings			
0.4.1	shall be paid for separately)	T/	200	
94.1	Powder coated aluminium (minimum thickness	Kg.	200	
05	of powder coating 50 micron)			
95	Providing and fixing 12 mm thick prelaminated			
	particle board flat pressed three layer or graded			
	wood particle board conforming to IS: 12823			
	Grade l Type ll, in panelling fixed in aluminum			
	doors, windows shutters and partition frames			
	with C.P. brass / stainless steel screws etc.			
	complete as per architectural drawings and			
05.1	directions of engineerin-charge.	C ~~~	20	
95.1	Pre-laminated particle board with decorative	Sqm	30	
0.0	lamination on both sides			
96	Providing and fixing glazing in aluminium			
	door, window, ventilator shutters and partitions			
	etc. with EPDM rubber / neoprene gasket etc.			
	complete as per the architectural drawings and			
	the directions of engineer-in-charge. (Cost of			
	aluminium snap beading shall be paid in basic			
06.1	item):	C	20	
96.1	With float glass panes of 5 mm thickness	Sqm	20	
07	(weight not less than 12.50 kg/sqm)			
97	Providing and fixing double action hydraulic			
	floor spring of approved brand and			
	manufacture conforming to IS: 6315, having			
	brand logo embossed on the body / plate with			
	double spring mechanism and door weight upto			

	125 kg for doors including aget of autting				
	125 kg, for doors, including cost of cutting				
	floors, embedding in floors as required and				
	making good the same matching to the existing				
	floor finishing and cover plates with brass pivot				
	and single piece M.S. sheet outer box with slide				
	plate etc. complete as per the direction of				
	Engineer-in-charge.				
97.1	With stainless steel cover plate minimum 1.25	Each	10		
,,,,	mm thickness	20011	10		
98	Filling the gap in between aluminium frame &				
	adjacent RCC/ Brick/ Stone work by providing				
	weather silicon sealant over backer rod of				
	approved quality as per architectural drawings				
00.4	and direction of Engineer-in-charge complete.		2000		
98.1	Upto 5mm depth and 5 mm width	Metre	2000		
99	Providing and fixing double glazed	Sqm	50		
	hermetically sealed glazing in aluminium				
	windows, ventilators and partition etc. with 6				
	mm thick clear float glass both side, having 12				
	mm air gap, including providing EPDM gasket,				
	perforated aluminium spacers, desiccants,				
	sealant (Both primary and secondary sealant)				
	etc. as per specifications, drawings and				
	direction of Engineer-in-charge complete.				
100	Providing and fixing Brass 100mm mortice	Each	10		
100	latch and lock with 6 levers without pair of	Lacii	10		
	handles (best make of approved quality) for				
	aluminium doors including necessary cutting				
101	and making good etc. complete.				
101	Providing and fixing aluminium round shape				
	handle of outer dia 100 mm with SS screws etc.				
	complete as per direction of Engineer-incharge				
101.1	Powder coated minimum thickness 50 micron	Each	10		
	aluminium				
102	Providing and fixing 12mm thick frameless	Sqm	10		
	toughened glass door shutter of approved brand	-			
	and manufacture, including providing and				
	fixing top & bottom pivot & double acting				
	hydraulic floor spring type fixing arrangement				
	and making necessary holes etc. for fixing				
	required door fittings, all complete as per				
	direction of Engineer in charge (Door handle,				
	lock and stopper etc. to be paid separately)				
103	Cleaning the sand stone surface and removing	Sam	50		
103		Sqm	30		
	dirt, dust, bird dropping, grease, oil, algae,				
	fungus, monkey beats, vegetable growth etc.,				
	including providing, applying and washing the				
	surface with liquidAmmonia Chemical of 5%				
	solution and other chemical cleaning agent as				
	approved by Archaeological Survey of India/				
	Engineer-in-charge, of approved brand and				
	manufacturer, with the help of required				
	scrubbers and also cleaning with machine				
	operated water jet mixed with desired quantity				
	of fine silica where ever required, without				
	causing any scratching/ damage to the stone				
	surface and finally washing the surface with				
<u> </u>	1		<u> </u>	<u> </u>	I

	clean water with the help of pressure jet				
	machine, complete in all respect, including				
	taking all precautions to safeguard ventilators,				
	windows, doors etc. by suitable covering so as				
	· ·				
	to avoid any damage to the building/structure,				
	all as per direction of Engineerin- charge (The				
	rate is inclusive of all materials & labours				
	involved except scaffolding).				
104	Providing and fixing 15 mm thick false ceiling	Sqm	80		
	tiles at all heights with integral densified	~ 1			
	calcium silicate reinforced with fibre and				
	natural filler false ceiling tiles of Size 595x595				
	mm of approved texture, design and patterns				
	having NRC (Noise Reduction coefficient) of				
	0.50 (minimum) as per IS 8225:1987, Light				
	reflectance of 85% (minimum). Non				
	combustible as per BS:476 (part-4), fire				
	performance as per BS:476 (part 6 &7),				
	humidity resistance of 100%, thermal				
	l · · · · · · · · · · · · · · · · · · ·				
	conductivity < 0.043 W/m K as per ASTM				
	518:1991,in true horizontal level on the				
	existing frame work consisting of T-sections				
	and Lsections suitably fixed according to tile				
	size as per direction of Engineer-in-charge.				
(B)	HORTICULTURE & LANDSCAPING				
105	Grassing with selection No. 1 Doob grass				
103					
	including watering and maintenance of the				
	lawn for 30 days or more till the grass forms a				
	thick lawn, free from weeds and fit for mowing				
	including supplying good earth, if needed (the				
	grass and good earth shall be paid for				
	separately).				
105.1	In rows 5 cm apart in both directions	Sqm	1000		
106	Filling mixture of earth and sludge or manure	Cum	150		
100	in the desired proportion in trenches, flooding	Cum	150		
	with water and leveling (cost of supplying earth				
	and sludge or manure and mixing excluded).				
(C)	Up Keeping of Maintenance Work				
107	Up-Keeping of maintenance work including				
	day to day complaint servicing related to				
	buildings, external landscape (Roads,				
	boundary, footpath etc.), round the clock				
	plumbing (internal/ external water supply,				
	sewerage, drainage etc.), round the clock STP				
	& WTP (operating Pumps, Motors, Starters and				
	other allied services on Main Water Supply				
	Pipeline Network and Tube well Pumps,				
	Booster Pumps, Main Reservoir Plant, UG				
	tanks, Overhead Tanks and STP including				
	noting of Pressure Readings, Chlorination at				
	various locations etc.), horticulture work (like				
	grass cutting by hand/ machine and				
	maintenance of flower beds, weeding,				
	watering, hedge plantation and other gardening				
	operations) and pest control etc. at all leads and				
	lifts as per the schedule and directions of				
	Engineer-In-Charge.				
				•	

		ı	1	ı	1
	Job work by specified nos. of workers with				
	necessary tools required for 08 hours per day				
	and 26 days per month as per the schedule. The				
	detail of manpower to be engaged for above				
	works as mentioned.				
	(The rates quoteded in financial bids would				
	cover all the liabilities of the Agency such as				
	cost of uniform, Bonus, ESIC, EPF and identity				
	cards of personnel deployed by the contractor				
	and all other statutory liabilities)				
107.1	Supervisor for Maintenance Services (01 Nos.	Per	312		
	per day)	Job			
	(As per deployment schedule to be approved by				
	Engineer-In-Charge)				
107.2	Mason for Civil Maintenance (01 Nos. per day)	Per	312		
107.2	(As per deployment schedule to be approved by	Job	312		
	Engineer-In-Charge)				
107.3	Carpenter for Civil Maintenance (01 Nos. per	Per	312		
107.5	day)	Job	312		
	(As per deployment schedule to be approved by				
	Engineer-In-Charge)				
107.4	Plumber for Civil Maintenance (02 Nos. per	Per	624		
107.4	` 1	Job	024		
	day)	300			
	(As per deployment schedule to be approved by				
107.5	Engineer-In-Charge)	Dom	1072		
107.5	Valve/ Pump Operator (PH) for Civil	Per Job	1872		
	Maintenance (06 Nos. per day)	300			
	(As per deployment schedule to be approved				
107.6	by Engineer-In-Charge)		212		
107.6	Painter for Civil Maintenance (01 Nos. per day)	Per	312		
	(As per deployment schedule to be approved by	Job			
105.5	Engineer-In-Charge)	D	212		
107.7	Welder for Civil Maintenance (01 Nos. per	Per	312		
	day)	Job			
	(As per deployment schedule to be approved by				
	Engineer-In-Charge)				
107.8	Sewerman for Civil Maintenance (01 Nos. per	Per	312		
	day)	Job			
	(As per deployment schedule to be approved				
	by Engineer-In-Charge)				
107.9	Helper/ Beldar/ Coolie for Civil Maintenance	Per	1872		
	(06 Nos. per day)	Job			
	(As per deployment schedule to be approved by				
	Engineer-In-Charge)				
107.10	Gardener/ Mali for Horticulture operations (08	Per	2496		
	Nos. per day)	Job			
	(As per deployment schedule to be approved by				
	Engineer-In-Charge)				
	Supply of Material				
108	Providing specified quaintly required for				
	upkeeping of maintenance work as per the				
	schedule				
108.1	Cement (PPC/OPC)	Bags	360		
108.2	Stone aggregate 10 mm nominal size	Cft.	300		
108.3	Stone aggregate 20 mm nominal size	Cft.	300		
108.4	Find Sand / Jamuna Sand	Cft.	300		
100.7	- III Suite / Vulliville Suite	U16.	200	İ	1

108.5	Coarse Sand	Cft.	300	
108.6	Bicks of standard side class designation 7.5	Nos.	3000	
108.7	19mm thick Commercial Board	Sqft	320	
108.8	6 mm thick commercial ply	Sqft	320	
108.9	12 mm commercial ply	Sqft	320	
108.10	Tape crete water proofing material	Ltr.	100	
108.11	White Cement (25 Kg. Bag)	Bags	12	
108.12	White Putty (20 Kg Bag)	Bags	12	
108.13	POP (25 Kg. Bag)	Bags	12	
108.14	Enamel Paint	Litre	100	
108.15	Acrylic Emulsion Paint	Litre	240	
108.16	Chrome Plated Brass Pressmatic/Press Pillar	Each	20	
100.10	Cock with Auto Closing System	Lacii	20	
(D)	Housekeeping Services			
109	Automated mechanized housekeeping services			
109	for I-Tech Building (Academiac and Guest			
	House Block), CRF Building, SATHI			
	Building, Staff Quaters, Basement and external			
	lanscape area at all leads and lifts by Sweeping,			
	Mopping, Scrubbing, Buffing, Vacuum			
	cleaning, Pressure washing etc. as per			
	frequency of cleaning chart and directions of			
	Engineer-In-Charge for period of one year			
	including: (The rates quoteded in financial bids			
	would cover all the liabilities of the Agency			
	such as cost of uniform, Bonus, ESIC, EPF and			
	identity cards of personnel deployed by the			
	contractor and all other statutory liabilities)			
109.1	Job work by specified nos. of housekeeping			
	workers required for 08 hours per day and 26			
	days per month as per the schedule.			
109.2	Facility Manager for Housekeeping Services	Per	312	
	(01 Nos. per day)	Job		
109.3	Helpdesk Executive for Housekeeping Services	Per	312	
	(01 Nos. per day)	Job		
109.4	Workers for Housekeeping Services (32 Nos.	Per	9984	
	per day)	Job		
	(As per Schedule to be approved by Engineer-			
	In-Charge).Staff to be trained to operate			
	machines in the schedule)			
109.5	Workers for Waste Collection Services (02 Nos.	Per	624	
	per day HK Staff)	Job		
	(As per Schedule to be approved by Engineer-			
	In-Charge).Staff to be trained to operate			
	machines in the schedule)			
110	Job work by various housekeeping machines/			
	equipments etc. required for 08 hours per day			
440 :	and 26 days per month as per the schedule.			
110.1	Battery Operated Ride on Scrubber Drier	Day	936	
110.5	(03 Nos. Per Day)		1010	
110.2	Back pack Vacuum Cleaner	Day	1248	
440 -	(04 Nos. Per Day)	_	4 - 4 -	
110.3	Single Disc Scrubber	Day	1248	
110 :	(04 Nos. Per Day)	-	0.1.5	
110.4	Heavy Duty High pressure Jet Washer	Day	312	
	(01 Nos. Per Day)			

111	Providing specified quantity of Housekeeping			
	chemicals, toiletries and consumable etc.			
	required as per the schedule.			
111.1	Bathroom Cleaner (R1)	Litre	240	
	(20 Ltr. Per Month)			
111.2	Hard Surface Cleaner/ All-purpose cleaning	Litre	240	
	agent (R2)			
	(20 Ltr. Per Month)			
111.3	Glass Cleaner (R3)	Litre	180	
	(15 Ltr. Per Month)			
111.4	Furniture polish (R4)	Litre	120	
	(10 Ltr. Per Month)			
111.5	Toilet bowl cleaner (R6)	Litre	240	
	(20 Ltr. Per Month)			
111.6	ScaleRemover (Removal of hard stains from	Litre	120	
	Bathroom walls and Fittings (R9)			
111.7	(10 Ltr. Per Month)	* *.	100	
111.7	Floor Cleaner for machines (R7 or Taski	Litre	120	
	Spiral)			
111 0	(10 Ltr. Per Month)	Litua	120	
111.8	Stainless steel polish (10 Ltr. Per Month)	Litre	120	
111.9	Wringers trolley (double Bucket 50Ltr, life 1	Each	6	
111.9	year)	Eacii	O	
111.10	Telescopic Rod (life 1 year)	Each	2	
111.10	Wash Room Cleaning kit holder within build	Each	6	
111.11	stool (life 1 year)	Lacii	U	
111.12	Sign Board (life 1 year)	Each	4	
111.13	Kentucky Mop (Life 6 month)	Each	20	
111.14	Dry Mop (Life 6 month)	Each	20	
111.15	Wiper (large) life 6 months	Each	20	
111.16	Wiper (Small) life 6 months	Each	20	
111.17	Dustbin capacity 100 ltr plastic (life 12 month)	Each	20	
111.18	Toilet Brush (life 3 months)	Each	48	
111.19	Dustbin foot operated for washrooms 15 ltr	Each	36	
	capacity (life 4 months)			
111.20	Floor Scrubbing Brush with Handle (life 3	Each	48	
	months)			
111.21	Plastic Mug (life 6 months)	Each	60	
111.22	Kentucky Mop Refill	Each	120	
111.23	Dry Mop Refill	Each	120	
111.24	Odonil 100gm	Each	240	
111.25	Spray pump	Each	120	
111.26	Floor Duster Full size	Doz	120	
111.27	Duster Check-Blue	Doz	60	
111.28	Duster Check-Green	Doz	60	
111.29	Vim Powder (1 kg Packet)	Kg.	60	
111.30	Scroch Brite (large)	Each	120	
111.31	Small chock pump	Each	120	
111.32	Plastic Juna	Each	144	
111.33	Broom Soft	Each	120	
111.34	Hard broom with long handle for Road	Each	60	
	sweeping			
111.35	Hand Gloves	Each	600	
111.36	Dustpan Plastic	Each	120	

111.37	Garbage bag big black	Kg.	120	
111.38	Garbage bag small Green	Kg.	120	
111.39	Glass squeeze	Each	24	
111.40	Feather Brush Heavy	Each	60	
111.41	Urinal Cubes	Kg.	120	
111.42	Urinal Screen V-Screen	Each	360	
111.43	Room Freshener	Each	240	
111.44	Hand wash liquid	Litre	240	
111.45	Glass Cleaning kit (life 6 month)	Each	4	
111.46	Hit/ Bagyon spray	Each	60	
111.47	Terranova Marble Maintainer	Ltr.	60	
	Total Rs.			

Special Conditions:

- 1. No labour huts shall be allowed in Sonipat campus of IIT Delhi, and nothing shall be paid extra on this account.
- 2. The contractor must visit the site of work /buildings before quoting the rates.
- 3. No labour to stay in Sonipat campus of IIT Delhi nothing shall be paid extra on this account.
- 4. Site shall be available as per directions of Engineer in Charge.
- 5. Quoted rates of participating agencies shall be inclusive of GST.